

**SURVEY & REMONUMENTATION** MECOSTA COUNTY REMONUMENTATION PROGRAM

APR 04 1996

CORNER APPROVED BY PEER GROUP ON NOVEMBER 4, 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

For corners in  
MECOSTA  
(County)

Located In: Corner Code #

Public Land Survey T 15N R 10W K-13

Property Controlling in Section S      T      R     

Miscellaneous Property in Sec. S      T      R     

95 JAN 19 P2 57

Caul Waldron  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4 Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5 Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on NOVEMBER 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
DEPUTY SURVEYOR, JOHN HODGSON, SET POST IN SEPT. 1837, CORNER POST PLACED 40.00 CHAINS (2640.00 FEET FROM SOUTH 1/4 CORNER SECTION 36 AND WITNESSED:  
BEECH 8" N53°E 43 LINKS (28.38 FEET)  
BEECH 8" N59°W 15 LINKS (9.90 FEET)

FIELD BOOK No. 1, PAGES 40 THRU 47 AT THE REGISTER OF DEEDS OFFICE SHOW THE FOLLOWING NOTES BY L. W. JUNE, COUNTY SURVEYOR, IN 1895, WHILE PERPETUATING THE GOVERNMENT SURVEY IN T15N-R9W "REWITNESSED".  
PINE STUMP 30" N70°E 38 LINKS (25.08 FEET)  
PINE STUMP 18" S35°E 57 LINKS (37.62 FEET)

MECOSTA COUNTY ROAD COMMISSION NOTES BY W. H. WRIGHT, COUNTY ENGINEER, DURING A ROAD SURVEY IN JULY 1936, NOTES CORNER AS "TILE AND CHARCOAL", AND BEING AT STATION 105+69, AND 116.0 FEET EAST OF CORNER FOR SECTION 2 AND 3, T14N-R9W.

A CERTIFICATE OF SURVEY BY THOMAS J. MUELLER, P.S. 25861, RECORDED IN LIBER 10, PAGES 784 AND 785, ON OCT. 23, 1979, NOTES CORNER AS, "FOUND 5/8" IRON".

A LAND CORNER RECORDATION CERTIFICATE BY THOMAS J. MUELLER P.S. 25861, RECORDED IN LIBER 1, PAGE 524, ON OCTOBER 23, 1979, NOTES CORNER AS, "FD. 5/8" IRON ON CENTERLINE TO NORTH AND CENTERLINE TO WEST, 111.36' EAST OF 5/8" IRON W/R.L.S. CAP", AND WITNESSED:

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990


16" POPLAR N74°E 13.41'  
FE. POST N75°W 110.95'  
16" TRIPLE MAPLE S82°W 141.17'  
3" POPLAR S65°W 33.55'

James G. Knapp  
CHAIRMAN  
DATE Nov. 4, 1993

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1/2" X 15" IRON ROD IN A STACK OF 3, 3" X 15" VITRIFIED TILES FILLED WITH SAND AND CHARCOAL, BURIED 3" BELOW GROUND SURFACE AND EXTENDING 2" ABOVE TOP OF TILES. CORNER IS AT THE P.I. OF A CURVE, 130th. AVE. (22' GRAVEL) NORTH AND 12 MILE ROAD (24' GRAVEL) WEST. AND APPROXIMATELY 115' EAST OF 130th. AVE. (22' GRAVEL) SOUTH.  
FOUND REMAINS OF PINE STUMP S35°E, 37.6 FEET AS NOTED BY L. W. JUNE, IN 1895 NOTES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K-13 - SECTION CORNER COMMON TO SECTION 35 AND 36, T15N-R9W  
FOUND 1/2" X 15" IRON ROD IN A STACK OF 3, 3" X 15" VITRIFIED TILES W/CHARCOAL AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
REMOVED 1/2" X 15" IRON AND 2 OF THE 3 TILES AND SET IN THE SAME A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT W/ONE TILE ON SLEEVE OF MONUMENT.

SET 60p SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF 7" WHITE OAK AZ. 10°, 49.35 FEET  
SET 60p SPIKE W/REMONUMENTATION TAG IN SOUTH SIDE OF 16" POPLAR AZ. 76°, 13.41 FEET (O.B.T.)  
SET 60p SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF 6" RED OAK AZ. 175°, 123.62 FEET  
SET 60p SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF 32" MAPLE AZ. 339°, 125.20 FEET



Signed by James G. Knapp Date January 19, 1995