

REMONUMENTATION

MECOSTA COUNTY REMONUMENTATION PROGRAM

NOV 18 1997

CORNER APPROVED BY PEER GROUP ON OCTOBER 24, 1996

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

For corners in MECOSTA (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T 15N R 10W	M-5 ✓
	T 15N R 09W	A-5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

97 SEP -5 P12:25

James G. Knapp
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on AUGUST 8, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST ON SEPT. 25, 1837, CORNER POST PLACED 40.00 CHAINS (2640 FEET) FROM 1/4 CORNER, SECTION 13 AND 18 AND WITNESSED:
 BEECH 7" S56°W 29 LINKS (19.14 FEET)
 BEECH 10" N50°W 31 LINKS (20.46 FEET)

IN 1895, LYMAN W. JUNE, COUNTY SURVEYOR, WAS APPOINTED BY THE COLFAX TOWNSHIP BOARD TO PERPETUATE THE GOVERNMENT SURVEY CORNERS IN T15N-R09W, AS RECORDED IN COUNTY SURVEYORS RECORD BOOK NO. 1, PAGES 281 AND 282. CORNER IS NOTED AS, "COR. SET BY LINES & MEASURE AT OLD COR. PINE 4" S60 W 19 SAME AS BY JAQUA".

IN JUNE, 1896, L. W. JUNE, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK No. 1, PAGE 10, NOTED CORNER AS, "TILE CORNER".

CORNER RECORDED AS PER P. A. 74 OF 1970, BY DUANE F. WOOD, P.S. 24625, ON SEPTEMBER 30, 1986, AND RECORDED IN LIBER 2, PAGE 130, AND NOTED AS, "FOUND 4" PIPE - ACCEPTED AS CORNER AND WITNESSED:

F. POLE	S70°E	52.00
12" TW. MAPLE	S15°W	18.03
12" MAPLE	WEST	11.58

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 OF 1990

James G. Knapp
 CHAIRMAN
 DATE OCT. 24, 1996

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD INSIDE OF STACK OF (3), 3" X 12" VITRIFIED CLAY TILE, BURIED 2" BELOW GROUND SURFACE. CORNER IS 0.5' SOUTHEAST OF 4 1/2" DIA. X 4 1/2' HIGH IRON PIPE, AND ON NORTH AND SOUTH OCCUPATION AND TREE LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


M-5 - SECTION CORNER COMMON TO SECTION 12, AND 13, T15N-R10W, AND SECTION 7, AND 18, T15N-R09W, FOUND 1/2" IRON ROD INSIDE OF A STACK OF (3), 3" X 12" VITRIFIED CLAY TILES, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE 1/2" IRON ROD AND INSIDE OF THE 3" X 12" VITRIFIED CLAY TILES, PROTRUDING 2" ABOVE GROUND SURFACE, AND WITNESSED:

SET 60d SPIKE W/REMONUMENTATION TAG IN S.W. SIDE OF UTILITY POLE
 SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF 12" TWIN MAPLE
 SET 60d SPIKE W/REMONUMENTATION TAG IN SOUTH SIDE OF 12" BEECH
 4 1/2" DIA. X 4 1/2' HIGH IRON PIPE
 SET 60d SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF 12" SOFT MAPLE

AZ. 124°	51.35 FEET
AZ. 200°	18.25 FEET
AZ. 283°	34.15 FEET
AZ. 310°	0.50 FEET
AZ. 340°	24.25 FEET

Signed by James G. Knapp Date JULY 7, 1997
 Surveyor's Michigan License No. 25853



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS AND LAND SURVEYORS, REVISED MARCH 1978
 ADAPTED FOR WORD PROCESSING MARCH, 1992