

**SURVEY & REMONUMENTATION**  
**MECOSTA COUNTY REMONUMENTATION PROGRAM**

FEB 26 1998

CORNER APPROVED BY PEER GROUP ON AUGUST 8, 1997

STATE OF MICHIGAN  
 COUNTY OF MECOSTA  
 RECEIVED FOR RECORD

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

'97 JUL 22 08:43

**SECTION**

For corners in MECOSTA (County) Located In: Corner Code #

1. Public Land Survey	T	15N	R	10W	H-05
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

4 Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

*James S. Knapp*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on JUNE 19, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, ABNER E. VANNESS, SET POST ON FEBRUARY 14, 1838. CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM CORNER COMMON TO SECTIONS 10, 11, 14 AND 15, AND NOTED AS, "SUGAR 20" DIA."

NOTES FROM CITY OF BIG RAPIDS FIELD BOOK NO.1, PAGE 140 - 141, BY L.W. JUNE, CITY SURVEYOR, NOTED AS, "OLD COR. MARKED BY LINE FENCES".

NOTES DATED SEPT. 1927, FROM BIG RAPIDS CITY ENGINEERS FIELD BOOK, DATED 1887, PAGE 32, NOTES 1/4 CORNER AS, "IRON PIPE 24' N.E. MAPLE 18".

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY DONALD R. VERBA, P.S. 13603, ON MAY 17, 1972, AND RECORDED IN LIBER 10, PAGE 37, CORNER NOTED AS, "FOUND 3/4" IRON".

CORNER NOTED AS PER P. A. 74 OF 1970, BY DONALD R. VERBA, P.S. 13603, ON MARCH 8, 1974, AND RECORDED IN LIBER 1, PAGE 88, AND NOTED AS, "FOUND IRON ON SIDE OF HILL", AND WITNESSED:

FOUND R.L.S. TAG (GLASS SURVEYS) SOUTH SIDE	36" MAPLE	AZ. 260°	24.70'
FOUND NAIL	4" ELM	AZ. 0°	11.11'

CORNER NOTED AS PER P. A. 74 OF 1970, BY GERALD J. GRAY, P.S. 17741, ON MARCH 24, 1975, AND RECORDED IN LIBER 1, PAGE 164, AND NOTED AS, "FND. 1" PIPE", AND WITNESSED:

4" ELM	N12°E	11.05
28" MAPLE	S65°W	24.05
6" CHERRY	S05°E	30.75

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY DUANE F. WOOD, P.S. 24625, IN MAY 1981, AND RECORDED IN LIBER 10, PAGE 984, CORNER NOTED AS, "1" PIPE", AND WITNESSED:

6" OAK	N30°E	32.2
32" MAPLE	N85°	23.1
CHERRY CLUSTER	N05°W	29.1

CORNER CALLED FOR IN SURVEY FOR CITY OF BIG RAPIDS JOB NO. 91014, BY, DUANE F. WOOD, P.S. 24625, ON FEB. 2, 1991, AND NOTES CORNER AS, "1" PIPE", AND WITNESSED:

6" OAK	N30°E	32.2
32" MAPLE	N85°	23.1
CHERRY CLUSTER	N05°W	29.1

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1" X 30" IRON PIPE, SURROUNDED WITH STONES, AND REMAINS OF OLD FENCE - SOUTH, ON S.E. LY SIDE OF HILL, AND A 1 1/4" PIPE, 12" ABOVE GROUND 0.4', EAST.

STATE PLANE COORDINATES AS DETERMINED BY GOURDIE/FRASER AND ASSOCIATES:  
 NORTH = 803201.62'  
 EAST = 12825287.60'

APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 of 1990  
*James S. Knapp*  
 CHAIRMAN  
 DATE AUG 8, 1997

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-05 - 1/4 CORNER COMMON TO SECTIONS 10, AND 15, T15N-R10W.  
 FOUND 1" X 30" IRON PIPE, SURROUNDED WITH STONES, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
 REMOVED THE 1" X 30" IRON PIPE, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, SET FLUSH WITH GROUND SURFACE, AND WITNESSED:

FOUND 50d SPIKE WITH TAG NO. 33439 IN WEST SIDE OF 12" BLACK OAK	AZ. 21°	32.70 FEET
FOUND 50d SPIKE WITH TAG NO. 33439 IN S.E. SIDE OF 10" WHITE ASH	AZ. 47°	20.22 FEET
FOUND SPIKE WITH GLASS SURVEYS TAG IN WEST SIDE OF 14" TWIN BLACK CHERRY	AZ. 183°	30.70 FEET
FOUND 50d SPIKE WITH TAG NO. 33439 IN NORTH SIDE OF 38" HARD MAPLE	AZ. 253°	22.52 FEET

Signed by James S. Knapp  
 Surveyor's Michigan License No. 25853

Date NOVEMBER 13, 1997

FORM APPROVED BY MICHIGAN STATE BOARD

