

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MECOSTA</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>16N</u> R <u>09W</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, CARL F. ROSER, in a field survey on DECEMBER 17, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 RESTORED W 1/4 COR S-32 IN LINE W/OLD N-S. FN TO S (FN COR-FN REMAINS W & S-IS 11' S) FOR EASTING & AT S EDGE OF 28'± WD. E-W GRVL RD (SOMEWHAT CURVING-ALMA LK RD) FOR NORTHING. THIS NORTHING FITS MEAN OF: LINE ACROSS FD L.W.JUNE(1913-TILE & IR) E 1/4 S-32(FD BOTH L.W.J. N.B.T STUMP REMAINS & TILE IR HIT BY GRADER) & L.W.J. STONE ON E-W 1/4 LINE S-32 (JUST W OF ALMA LK), PROJECTED W'LY; & LINE ACROSS FD CTR & W 1/8 COR ON E-W 1/4 LINE S-31 (SEE CERT SUR, L.11-PG 58 & 59, W.R.BYL, DATED 5-26-82 & CERT SUR, L.10-PG 541, G.J.GRAY, DATED 6-07-78) PROJECTED E'LY. THIS EASTING (IN LINE W/OLD FN LOOKING S) FITS L.W.JUNE DIST E 1-MILE & 1928 DIST W 1/2 MILE TO CTR S-31 (SEE LOOSE PG IN DRAWER OF OLD CO SURVEYORS NOTES AT REG OF DEEDS). THE 1/4 COR RESTORATION, AS NOTED ABOVE, FITS PROBABLE 1838 U.S. G.L.O. LINE TREE (18" PINE) N 3.17 CHAINS (NOW A DEFINITE 24"± W PINE STUMP REMAINS-LG HUMMOCK) RECORD & MEA. MR. VERN CARE (68 YRS OLD, LIVES ON E 3/4 OF S 1/2 S-31) SAYS "DID WE FIND THE OLD CORNER"; HE LOOKED AT OLD FN COR 11' S & SAYS "MAYBE HIS FAMILY MOVED THE FENCE BACK A LITTLE WHEN ALMA LK RD WAS CONSTRUCTED IN EARLY 1930'S"; MR. LES NEWBERRY (69 YRS OLD, LIVES ON NE-NW S-31) SAYS HE REMEMBERS "SEEING A PIPE OR SOMETHING LIKE THAT" (B. CONTINUED ON BACK OF THIS FORM.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12
 SET STD MON (ALUM CAP ON 1" X 36" GAL IR PIPE)
 4" MAPLE N40°W 67.40
 7" MAPLE IN CLP 3 N45°E 84.63
 3" W OAK S50°E 30.15
 CTR E-W GRAVEL RD (CURVING) NORTH 14'±
 4" MAPLE S45°W 36.56
 DROVE 5/8" X 34" REROD W/RLS CAP
 SET CED POST W/LOC TAG S02°08'W 16.50
 FD 1/2" REROD N02°43'W 24.84
 DROVE 5/8" X 34" REROD W/RLS CAP
 N02°01'E 50.00

Signed by Carl F. Roser 02/10/88 Date _____

Surveyor's Michigan License No. 12028



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS
 REVISED JAN., 1983

ITEM "B" ABOVE IS CONTINUED ON BACK OF THIS FORM