

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

MECOSTA

(County)

Located In:

Corner Code ~~##~~

1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S 32 T 16N R 9W 3, 4  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S 32 T 16N R 9W \*576.5'S COR CODE 4  
Property in Sec. S 32 T 16N R 9W \*\*\*1178'W OF D-12

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, CARL F. ROSER, in a field survey on DECEMBER 17, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

C. CONTINUED

A. Description of original monument and accessories and/or subsequent restoration:

- |   |   |
|---|---|
| DROVE 5/8" X 34" REROD W/RLS CAP. SET CED POST. | DROVE 5/8" X 34" REROD W/RLS CAP. SET CED POST W/LOC TAG. |
| 30" R OAK N55°W 17.00                           | 14" MAPLE N15°W 27.6'                                     |
| 6" W PINE N25°E 26.81                           | 3" R OAK N65°E 28.1'                                      |
| 10" R OAK S15°E 15.65                           | 10" R OAK S85°E 27.1'                                     |
| NW EDGE ALMA LK DUE S 22'±4'                    | SE EDGE ALMA LK DUE N 70'±5'                              |
| NW EDGE ALMA LK DUE E 25'±6'                    | SE EDGE ALMA LK DUE W 25'±4'                              |
|   | FD 1/2" IR W/RLS CAP S08°W 24.96                          |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 3 DROVE 5/8" X 34" REROD FOR SW COR OF NW 1/4-NW 1/4 S-32. OLD E-W FENCE REMAINS, E IS 57'± N.
- 4 DROVE 5/8" X 34" REROD FOR SE COR OF NW-NW OF S-32.
- \* DROVE 5/8" X 34" REROD FOR MEANDER COR ON W LINE OF SE 1/4 OF NW 1/4 OF S-32 AND N SIDE ALMA LK; S00°25'E, 576.5' FROM CTR OF NW 1/4 OF S-32.
- \*\*\* DROVE 5/8" X 34" REROD FOR MEANDER COR ON S LINE OF SE 1/4 OF NW 1/4 OF S-32 AND E SIDE OF ALMA LK; N89°22'W, 1178.14' FROM CTR OF S-32. CALC POSITION (IN LAKE) OF SW COR OF SE-NW OF S-32 WOULD BE N89°22'W, 221.43' FROM ABOVE M.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |
|--|---|
| DRIVE 5/8" X 34" REROD W/RLS CAP & SET CED POST. | DROVE 5/8" X 34" REROD W/RLS CAP; SET CED POST. |
| 11" & 7" MAPLE N20°W 12.92                       | 16" R OAK N45°W 28.98                           |
| 11" & 8" BEECH S70°E 14.67                       | 6" R OAK N30°E 45.97                            |
| 3" R OAK IN CLUMP 3 S20°W 6.67                   | 10" R OAK S60°W 10.73                           |
| CTR N-S TRAIL DUE W 195'±3'                      |   |

Signed by Carl F. Roser 02/10/88 Date \_\_\_\_\_

Surveyor's Michigan License No. 12028

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

