

SURVEY & REMONUMENTATION COMMISSION
 APR 10 1998

MECOSTA COUNTY REMONUMENTATION PROGRAM
 CORNER APPROVED BY PEER GROUP ON 12 DECEMBER 1994

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

or corners in
 Mecosta
 (County)

Located In: Corner Code #

Public Land Survey T16N R0W A-7
 T R
 T R
 T R
 Property Controlling S T R
 in Section S T R
 Miscellaneous S T R
 Property in Sec. S T R

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED

'94 DEC 22 P1:26

Carl Waldron
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

Matthew McClung in a field survey on December 11, 1994
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
 The original corner was set by deputy surveyor John Hodgson on 13 October 1837. Volume 2 Page 138 of Field Notes, set wood post.
 10" Beech N67W 53 lks.
 8" Beech S40W 13lks.

Page 175 County survey Records. Date 4-28-15, by Willets, recorded as a 3" tile.
 Corner Fence Post NE 37.0'
 Elm Stump West 49.8'

continued on back page

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 20 penny spike at surface. Removed spike and dug to 24" below surface and found nothing. Hired backhoe and dug to 3' and found solid clay tile. Placed Mecosta County Monument over Tile 6" below surface.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner A-7. Mecosta County Monument, which is a 3" brass cap mounted on a 2 1/2" pipe, 36" in length, and is accepted as a careful and faithful reestablishment of the position of the original corner.
 Power Pole N54E 99.14 feet.
 Power Pole S62E 78.41 feet.
 East most of 3 telephone pedestals S34E 51.87 feet.
 20" White Ash S12W 216.03 feet.

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 349 of 1990
James J. Knapp
 CHAIRMAN
 DATE DEC. 12, 1994

Surveyed by *Matthew McClung* Date December 11, 1994
 Surveyor's Michigan License No. 13037

H. F. Anderson on 10-1932. Fence post West 26.5 feet.

Road Plans April 30, 1919, 3" tile. Corner fence post NE 37.0' Elm Stump
West 49.8' Fence West 26.5'