

MECOSTA COUNTY REMONUMENTATION PROGRAM  
 CORNER APPROVED BY PEER GROUP ON 12 DECEMBER 1994

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF MECOSTA  
 RECEIVED FOR RECORD

corners  
 Mecosta  
 (County)

APR 10 1995

COMMISSION

Located In: \_\_\_\_\_ Corner Code ## \_\_\_\_\_  
 T 16N R 9E W  
 T \_\_\_\_\_ R \_\_\_\_\_ A 9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

'94 DEC 22 P1:26

Carl Waldron  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Matthew McClung, in a field survey on December 11, 1994 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor John Hodgson on 13 October 1837. Volume 2 field notes, set Post.  
 16" Hemlock S45W 18 lks.  
 15" Hemlock N59W 171 lks.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod and 3' tile filled with cinders at surface. Removed tile and bent rod north. Set Corner along south side of tile to a depth of 30" and placed Mecosta County Monument over tile.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A-9. Mecosta County Monument, which is a 3" brass cap mounted on a 1/2" pipe, 36" in length, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 24" Red Oak N15E 4 feet  
 10" Soft maple West 8.37 feet  
 4" White Pine S10W 10.9 feet.  
 24" White Oak S75E 9.25 feet  
 Down Cedar fence post at corner.

APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 of 1990

James M. Knapp  
 CHAIRMAN  
 DATE DEC. 12, 1994

Surveyed by Matthew McClung Date December 11, 1994  
 Surveyor's Michigan License No. 13037