

MECOSTA COUNTY REMONUMENTATION PROGRAM
CORNER APPROVED BY PEER GROUP ON 12 DECEMBER 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

'94 DEC 22 P1:26

Carl Waldron
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Mecosta
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 16N R 09W pm C-8
- T 16N R 10W
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Matthew McClung, in a field survey on December 11, 1994
do hereby certify that under Requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor Abner Van Ness on 26 March 1838. Volume 2 page 162 Field notes, Set Post.
Beech 8" N48W 17 lks.
Beech 8" N14E 14 lks.

Liber 2 page 348, Roser dated 1-15-88, found 1/2" rod in 3" tile buried 1/2' deep in open field, inline with road to South and approximate center line of split between 60' fence remains. Set Cedar Location post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod and tile 1' below surface. Placed Mecosta County Monument 4" above surface over center of Tile and rod.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C-8. Mecosta County Monument, which is a 3" brass cap mounted on a 2 1/2" pipe, 36" in length, and is accepted as a careful and faithful reestablishment of the position of the original corner.
14" White Ash S05W 47.74 feet. O.B.T
8" Apple S25W 42.03 feet. O.B.T.
6" Maple S20E 57.50 feet. O.B.T.
DNR post West 1.0 feet.

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James J. Knapp
CHAIRMAN
DATE Dec. 12, 1994

Signed by Matthew McClung Date December 11, 1994
Surveyor's Michigan License No. 13037