

MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON JUNE 11, 1999

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

OCT 28 1999

SECTION

'99 OCT -8 P3:05

For corners in
MECOSTA
(County)

Located In: Corner Code #

- 1. Public Land Survey T 16N R 09W F-07
- T _____ R _____
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ _____
- S _____ T _____ R _____
- S _____ T _____ R _____
- S _____ T _____ R _____
- 3. Miscellaneous S _____ _____
- S _____ T _____ R _____
- S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Joann Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, JAMES G. KNAPP, in a field survey on APRIL 21, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST IN THE SECOND QUARTER OF 1838. CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM 1/4 CORNER COMMON TO SECTIONS 20 AND 21, AND WITNESSED: BEECH 8" S39°E 22 LINKS (14.52 FEET) BEECH 10" N64 1/2°W 50 LINKS (33.00 FEET)

NOTES IN COUNTY SURVEYOR'S BOOK NO. 1, PAGE 175, BY WALTER WILLITS, COUNTY SURVEYOR, DATED APRIL 28, 1915, NOTES CORNER AS, "TILE", AND WITNESSED: ELM 8" N51°W 64' ELM 4" S03°E 41.5'

CORNER RECORDED AS PER P.A. 74 OF 1970, BY GERALD J. GRAY, P.S. 17741 ON AUG. 14, 1979, IN LIBER 1, PAGE 504, AND NOTED AS, "FOUND OLD WOOD STAKE AND SET BOLT SPIKE", AND WITNESSED: N50°W 48.4' FENCE POST SOUTH 24.75' 10" MAPLE N45°E 68.5' 6" PINE

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 74 of 1970
James G. Knapp
SURVEYOR
DATE JUNE 11, 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 8" LAG SCREW, BURIED 10" DEEP, AT 14" FOUND 1/2" IRON ROD ALONG SIDE A 2" SQUARE WOODED STAKE, SURROUNDED WITH STONES, 1.0' SOUTH OF CENTERLINE OF 21 MILE (22' BITUMINOUS) AND IN LINE WITH CENTER OF 155TH AVE (18' GRAVEL - NORTH) AND REMAINS OF FENCE - SOUTH.

SET REMONUMENTATION MONUMENT AND HIGHWAY MONUMENT BOX, 1.0' SOUTH OF CENTERLINE, DURING BITUMINOUS PAVING OF 21 MILE ROAD (22' BITUMINOUS) ON APRIL 29, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-07, 1/4 CORNER COMMON TO SECTIONS 16 AND 21, T16N-R09W.
FOUND 8" LAG SCREW, BURIED 10" DEEP, AT 14" FOUND 1/2" IRON ROD ALONG SIDE A 2" SQUARE WOODED STAKE, SURROUNDED WITH STONES, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
REMOVED THE 8" LAG SCREW, AND PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE 1/2" IRON ROD, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:
SET 60d SPIKE W/REMONUMENTATION TAG IN N.W. SIDE OF 14" JACK PINE AZ. 38°, 68.50 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF 14" ASH AZ. 152°, 59.96 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF 18" ELM AZ. 222°, 33.37 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN S.W. SIDE CORNER FENCE POST AZ. 312°, 59.65 FEET
FOUND DOUBLE HEADED NAIL



Signed by James G. Knapp
Surveyor's Michigan License No. 25833

Date SEPTEMBER 24, 1999