

MECOSTA COUNTY REMONUMENTATION PROGRAM

OCT 26 1999

CORNER APPROVED BY PEER GROUP ON NOVEMBER 12, 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

SECTION

For corners in

MECOSTA (County)

Located In:

Corner Code #

99 JUN -1 P3:45

Joan Brown REGISTER OF DEEDS

Table with 4 columns: Section, Located In, Corner Code #, and a blank column. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4 Lot No. Recorded Plat
5 Private Claims

I, JAMES G. KNAPP, in a field survey on JULY 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked in the intersection of column G and row 3.

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST IN SECOND QUARTER 1838, CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM 1/4 CORNER, SECTION 9 AND 10, AND WITNESSED: HEMLOCK 12" N27°E 10 LINKS (6.60 FEET) HEMLOCK 10" S76°W 31 LINKS (20.46 FEET)

ON MARCH 24 THRU 26, 1902, L. W. JUNE, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK NO. 1, PAGE 103, (FIELD BOOK NO. 5, PAGE 26), NOTES CORNER AS, "TILE", AND SHOWS A DISTANCE OF 39.70 CHAINS (2620.20 FEET TO EAST 1/4 CORNER, SECTION 9.

ON APRIL 28, 1915, WALTER WILLITS, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK NO. 1, PAGE 174, NOTES CORNER AS, "IRON", AND WITNESSED: PINE ST. N34°E 54' COR. FENCE POST W. 33'

CORNER RECORDED AS PER P. A. 74 OF 1970, BY GERALD J. GRAY, P.S. 17741, ON AUG. 14, 1979, IN LIBER 1, PAGE 501, AND CORNER NOTED AS, "END. LARGE BOLT/RESET ROD", AND WITNESSED: "X" IN FLAT ROCK WEST 134.90' CENTERLINE ASHFAULT WEST 5.30' 8" POPLAR S20°W 130.65'

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp CHAIRMAN DATE NOV. 12, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 18" RE-BAR, 2" BELOW BITUMINOUS ROAD SURFACE, AT 10" DEEP FOUND 1-1/2" X 1-1/2" SQUARE HEAD BOLT 24" LONG.

CORNER IS 5.2' EAST OF CENTERLINE OF 150TH AVENUE (20' BITUMINOUS).

MEASURED DISTANCE TO G-04 = 2607.84'

SET COUNTY MONUMENT AND HIGHWAY MONUMENT BOX DURING BITUMINOUS PAVING ON JULY 3, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-03, COMMON TO SECTIONS 3, 4, 9 AND 10, T16N-R09W. FOUND 1/2" X 18" RE-BAR, 2" BELOW BITUMINOUS ROAD SURFACE, AT 10" DEEP FOUND 1-1/2" X 1-1/2" SQUARE HEAD BOLT 24" LONG., AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

LEFT BOLT IN PLACE, AND PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE TOP OF IT, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:

- SET 60d SPIKE W/REMONUMENTATION TAG IN NORTH SIDE OF 12" RED PINE AZ. 78°, 50.24 FEET
15" WALNUT AZ. 196°, 130.70 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN NORTH SIDE OF 14" RED PINE AZ. 274°, 127.33 FEET
SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF 14" RED PINE AZ. 336°, 114.60 FEET

Signed by James G. Knapp Date APRIL 26, 1999
Surveyor's Michigan License No. 25853

