

OCT 23 1999

MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON NOVEMBER 13, 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

For corners in

MECOSTA (County)

Located In:

Corner Code #

- 1. Public Land Survey T 16N R 09W G-05
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

'99 OCT -8 P3:05

James Brown REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4 Lot No. Recorded Plat
5 Private Claims

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and a central dot.

I, JAMES G. KNAPP, in a field survey on JULY 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST IN SECOND QUARTER 1838, CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM 1/4 CORNER, SECTIONS 15 AND 16, AND WITNESSED: BEECH 8" N31°E 31 LINKS (20.46 FEET) BEECH 8" S37°E 25 LINKS (16.50 FEET) ON MARCH 24 THRU 26, 1902, L. W. JUNE, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK NO. 1, PAGE 103, (FIELD BOOK NO. 5, PAGES 26 - 31), NOTES CORNER AS, "TILE", AND SHOWS A DISTANCE OF 39.82 CHAINS (2628.12 FEET) TO EAST 1/4 CORNER, SECTION 9. ON APRIL 28, 1915, WALTER WILLITS, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK NO. 1, PAGE 1/4, NOTES CORNER AS, "IRON", AND WITNESSED: MAPLE 2" N35°E 40'. ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, BY E. E. SOURS, DATED APRIL 6, 1918, NOTES CORNER AS BEING AT STA. 58+31.8, AND THE EAST 1/4 CORNER AT STA. 84+89.1, SECTION 16. CORNER RECORDED AS PER P. A. 74 OF 1970, BY HENRY J. MULDER, P.S. 25862, ON APR. 19, 1984, IN LIBER 2, PAGE 081, AND CORNER NOTED AS, "END. IRON BUGGY BRACE FROM FOUND 1 WITNESS, NEAR E. EDGE PAV'T.", AND WITNESSED: N45°E, 39.35' NAIL IN W. SIDE 18" MAP. N45°W, 41.6' FACE SIGN POST S45°W, 8.78' R.R. SPIKE IN C/L RD. S35°E, 50.09' NAIL IN NE SIDE TRIP. 6" ELM

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp CHAIRMAN DATE Nov. 13, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1-1/2" OVAL SHAPED X 28" IRON ROD, ALONG SIDE OF 5/8" X 30" IRON ROD INSIDE OF A VITRIFIED CLAY TILE, SURROUNDED BY STONES AT SURFACE OF ROAD, 5.0' EAST OF CENTERLINE OF 150TH AVENUE (21' BITUMINOUS) AND IN LINE WITH CENTER OF 22 MILE ROAD (22' GRAVEL - EAST AND WEST).

MEASURED DISTANCE TO G-04 = 2618.68'

SET REMONUMENTATION MONUMENT AND HIGHWAY MONUMENT BOX, 6.4' WEST OF CENTERLINE, DURING BITUMINOUS PAVING OF 150TH AVENUE (20' BITUMINOUS) ON JULY 3, 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-05, CORNER COMMON TO SECTIONS 9, 10, 15 AND 16, T16N-R09W. FOUND 1-1/2" OVAL SHAPED X 28" IRON ROD, ALONG SIDE OF 5/8" X 30" IRON ROD INSIDE OF A VITRIFIED CLAY TILE, SURROUNDED BY STONES AT SURFACE OF ROAD, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. REMOVED IRONS, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED: SET 60d SPIKE W/REMONUMENTATION TAG IN N.W. SIDE OF 22" MAPLE AZ. 48°, 39.60 FEET (O.B.T.) SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF TRIPLE 12" ELM AZ. 160°, 49.94 FEET SET 60d SPIKE W/REMONUMENTATION TAG IN EAST SIDE OF UTILITY POLE AZ. 202°, 152.42 FEET SET 60d SPIKE W/REMONUMENTATION TAG IN NORTH SIDE OF 6" ELM AZ. 262°, 89.17 FEET

Signed by James G. Knapp

Date SEPTEMBER 24, 1999

Surveyor's Michigan License No. 25853

