

# SURVEY & REMONUMENTATION

SEP 1 2 1996

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

For corners in  
MECOSTA

(County)

Located In:

Corner Code #

- |                                    |                           |             |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey              | T <u>16N</u> R <u>09W</u> | <u>6-11</u> |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |

'96 AUG 21 AIO:36

*James Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL T. KIISKILA, in a field survey on NOVEMBER 21, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

6-11  
U.S. G.L.O. SURVEY BY  
J. HODGSON IN 1838; SET POST  
CORNER SEC'S. 27, 28, 33 & 34  
BEECH 12 S59°W 13  
DO 12 N45°E 33

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

6-11  
REESTABLISHED THE NE COR OF  
SEC 33 IN LINE WITH OLD FENCE  
REMAINS SOUTH & 33' NORTH OF  
OLD E-W FN. REMAINS. CTR OF  
E-W WINDING SAND ROAD IS 10'  
NORTH.

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990

*James H. Knapp*  
CHAIRMAN  
DATE JAN. 25, 1996

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

6-11  
SET MECOSTA CO. MON.  
6" R. OAK N05°E 30.2'  
11" R. OAK N60°E 34.1'  
8" TW. B. CHERRY S45°E 42.4'  
6" ELM S65°W 41.6'  
SET CARBONITE POST W/LDC  
TAG SOUTH 33'  
FD 1/2" x 18" RERDD SB. 31.50'



Signed by Carl T. Kiiskila Date 7-31-96

Surveyor's Michigan License No. 33981