

MECOSTA COUNTY REMONUMENTATION PROGRAM

OCT 26 1999

CORNER APPROVED BY PEER GROUP ON OCTOBER 8, 1999

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

SECTION

For corners in

MECOSTA (County)

Located In:

Corner Code #

Table with 3 columns: Item description, T/R/S, and Corner Code #. Includes Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

99 OCT 21 10:04

Signature of Joseph Brown, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4 Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and a central dot in cell G3.

I, JAMES G. KNAPP, in a field survey on APRIL 10, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST IN THE SECOND QUARTER OF 1838. CORNER POST PLACED 39.90 CHAINS (2633.40 FEET) FROM N.E. CORNER AND N.W. CORNER, SECTION 10, AND WITNESSED: HEMLOCK 8" S45°W 09 LINKS (5.94 FEET) HEMLOCK 8" N49°W 13 LINKS (8.58 FEET)

CORNER RECORDED AS PER P. A. 74 OF 1970, BY JERRY L. WILCOX, P.S. 14102, ON FEB. 8, 1983, IN LIBER 2, PAGE 66, AND NOTED AS, "FOUND 1/2" IRON IN TILE 1'+/- SOUTH OF CORNER FENCE POST (FENCE N-S & WEST)", AND WITNESSED:

SOUTH, 23.66' 5" CEDAR
NORTH, 1.00' CORNER FENCE POST
S60°W, 10.74' 8" HEMLOCK
WEST, 45.73' 5" CEDAR

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 of 1990

Signature of James G. Knapp, CHAIRMAN, DATE Oct. 8, 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD, INSIDE OF A VITRIFIED CLAY TILE, FILLED WITH CHARCOAL, 1' SOUTH OF REMAINS OF FENCE CORNER (FENCE NORTH AND WEST).

PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE 1/2" IRON ROD, INSIDE OF THE CLAY TILE, PROTRUDING 5" ABOVE GROUND SURFACE, SURROUNDED WITH STONES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-03, 1/4 CORNER COMMON TO SECTIONS 3 AND 10, T16N-R09W. FOUND 1/2" IRON ROD, INSIDE OF A VITRIFIED CLAY TILE, FILLED WITH CHARCOAL, 1' SOUTH OF REMAINS OF FENCE CORNER (FENCE NORTH AND WEST), AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE 1/2" IRON ROD, INSIDE OF THE CLAY TILE, PROTRUDING 5" ABOVE GROUND SURFACE, SURROUNDED WITH STONES, AND WITNESSED:

SET 60d SPIKE W/REMONUMENTATION TAG IN NORTH SIDE OF 10" CEDAR AZ. 110°, 64.95 FEET
FOUND NAIL IN EAST SIDE OF 8" CEDAR AZ. 186°, 23.66 FEET (O.B.T.)
FOUND NAIL IN SOUTH SIDE OF 8" CEDAR AZ. 284°, 45.73 FEET (O.B.T.)
SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF 8" MAPLE AZ. 312°, 28.42 FEET

Signed by James G. Knapp
Surveyor's Michigan License No. 25953

Date OCTOBER 12, 1999

LIBER 101 PAGE 211

