

SEP 12 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MECOSTA

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 16N | R | 09W | H-11 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED FOR RECORD

'96 AUG 21 A10:36

Joann Brown
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL T. KIISKILA, in a field survey on FEBRUARY 6, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-11	H-11 CONT
US GLO, J.HODGSON 1838;	WAS MADE FOR THIS OLD STAKE
ELM 10 S57°W 08	AND ELM ROOTS AS DESCRIBED IN
MAPLE 16 S22°E 16.	THE COUNTY SURVEYORS RECORD
L.W.JUKE, JAN 15-16, 1896; "TILE	#1, BUT NO EVIDENCE OF THIS
COR? (AN OLD STAKE IS 125 L.	POST OR ELM ROOTS WERE FOUND.
SOUTH & 8 L. W IS CLAIMED AS	
ORIGINAL - ELM ROOTS WERE	
FOUND IN PLACE FOR ORIGINAL	
ELM B.T.) A THROUGH SEARCH	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11	H-11 CONT
RECOVERED 1/2" x 45" SMOOTH	
IRON ROD LYING ON GROUND. DUG	
& FD 2-3" x 12" VIT TILES	
FILLED W/CINDERS. THE THIRD	
TILE ON TOP WAS BROKEN. FD	
REMAINS OF WOOD POST BURIED.	
ADDED MECOSTA CO. MON. ON EAST	
EDGE OF 2 BURIED TILES. COR OF	
OLD FN'S E-W-S IS 33' ± 2'	
SOUTH.	

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990

James M. Knapp
 CHAIRMAN
 DATE JAN. 25, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11	H-11 CONT
FD 1/2" IRON ROD IN 2-VIT.	
TILES, ADDED MECOSTA CO. MON.	
SET CEDAR POST.	
4" R.OAK N55°W 8.0'	
4" R.OAK N15°E 7.9'	
3" R.OAK S75°E 15.2'	
10" R.OAK S50°W 5.3'	



Signed by Carl T. Kiiskila

Date 7-31-96

Surveyor's Michigan License No. 33981