

Seq. 1

SURVEY & REMONUMENTATION
APR 10 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 REGISTER OF DEEDS

94 DEC 22 P1:26

Carl Waldron
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Public Land Survey: T 16N R 10W Corner Code C-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 Property Controlling in Section: S _____ T _____ R _____
 S _____ T _____ R _____
 Miscellaneous: S _____ T _____ R _____
 Property in Sec.: S _____ T _____ R _____

Lot No. _____, Recorded Plat _____
 Private Claims _____

Matthew McClung in a field survey on December 11, 1994
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the recent manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor Abner Van Ness on 26 March 1838. Volume 2 page 162 Field notes, Set Post.
 Beech 8" N48W 17 lks.
 Beech 8" N14E 14 lks.

Under 2 page 348, Roser dated 1-15-88, found 1/2" rod in 3" tile buried 1/2' deep in open field, inline with road to South and approximate center line of split between 60' fence remains. Set Cedar Location post.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod and tile 1' below surface. Placed Mecosta County Monument 1" above surface over center of Tile and rod.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C-8. Mecosta County Monument, which is a 3" brass cap mounted on a 1/2" pipe, 36" in length, and is accepted as a careful and faithful reestablishment of the position of the original corner.
 14" White Ash S05W 47.74 feet. O.B.T.
 8" Apple S25W 42.03 feet. O.B.T.
 6" Maple S20E 57.50 feet. O.B.T.
 DNR post West 1.0 feet.

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 343 of 1990
James S. Knapp
 CHAIRMAN
 DATE Dec. 12, 1994

Surveyed by Matthew McClung Date December 11, 1994
 Surveyor's Michigan License No. 13037