

MECOSTA COUNTY REMONUMENTATION PROGRAM

OCT 26 1999 CORNER APPROVED BY PEER GROUP ON NOVEMBER 13, 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

SECTION

For corners in MECOSTA (County)

Located In:

Corner Code #

'99 OCT -8 P3:05

Joan Brown REGISTER OF DEEDS

- 1. Public Land Survey T 16N R 10W D-13
2. Property Controlling In Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, JAMES G. KNAPP, in a field survey on OCTOBER 19, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST ON OCT. 14, 1837. POST PLACED 40.00 CHAINS (2640.00 FEET) FROM S.E. CORNER, SECTION 32, AND WITNESSED: SUGAR 8" N65°E 09 LINKS (5.94 FEET) SUGAR 14" N22°W 05 LINKS (3.30 FEET)

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, DATED MAY 1930, NOTE, "1/4 LINE F. N.", AT STATION 28+84 WITH N.W. CORNER, SECTION 5, T15N-R10W BEING AT STATION 0+00.

CORNER RECORDED AS PER P.A. 74 OF 1970, BY DOUGLAS W. HOOTH, P.S. 7966, IN LIBER 1, PAGE 283, ON JAN. 27 1977 AND NOTED AS, "FOUND 1/2" PIPE, BURIED .5 FT., IN CTR. OF RD., & IN LINE WITH OLD FENCE & TREE LINE NORTH", AND WITNESSED: N50°E 6" TWN. APPLE 41.32' S35°W 4" ELM 33.60' N45°W 12" IRONWOOD 52.39' N20°W 12" HAWTHORNT (TRIPLE) 36.35'

CORNER RECORDED AS PER P.A. 74 OF 1970, BY DUANE F. WOOD, P.S. 24625, IN LIBER 2, PAGE 203, ON FEB. 19 1988 AND NOTED AS, "FOUND 1/2" REBAR WITH ID CAP 19305", AND WITNESSED: P.S. 24625, IN LIBER 2, PAGE 203, ON FEB. 19 1988 AND NOTED NORTH 1/4 CORNER, SEC.5, T15N,R10W N89°-55'-27"W, 229.38' CENTERLINE SOUTHBOUND LANE OF U.S. 131 FREEWAY, WEST, 49.3'

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY DUANE F. WOOD, P.S. 24625, ON MAR. 28, 1988, AND RECORDED IN LIBER 11, PAGE 254 - 255, AND NOTES CORNER AS, "S. 1/4 CORNER, SEC. 32, T16N-R10W", AND SHOWS A DISTANCE OF 229.38' WEST TO THE NORTH 1/4 CORNER, SECTION 5, T15N-R10W.

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 OF 1990

James G. Knapp CHAIRMAN DATE NOV. 13, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND 1/2" REBAR WITH ID CAP, "J.E.P 19305", ON EAST BACK SLOPE OF ROAD DITCH FOR SOUTH BOUND U.S. 131 EXPRESSWAY. SET CARSONITE WITNESS POST ON EAST SIDE OF MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13, SOUTH 1/4 CORNER SECTION 32, T16N-R10W. FOUND 1/2" RE-BAR WITH ID CAP, "J.E.P 19305, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. PLACED OVER THE 1/2" RE-BAR, A STANDARD MECOSTA COUNTY REMONUMENTMENT MONUMENT, AND WITNESSED: FOUND RAILROAD SPIKE IN WEST SIDE UTILITY POLE AZ. 17° 276.92 FEET N.E. CORNER, SECTION 5, T15N-R10W, MECOSTA COUNTY MONUMENT AZ. 90° 2418.91 FEET NORTH 1/4 CORNER, SECTION 5, T15N-R10W, (MECOSTA COUNTY MONUMENT) AZ. 270° 229.29 FEET CENTERLINE SOUTHBOUND LANE U.S. 131 EXPRESSWAY AZ. 270° 49.30 FEET

Signed by James G. Knapp Date SEPTEMBER 23, 1999 Surveyor's Michigan License No. 25853

