

SURVEY & REMONUMENTATION MECOSTA COUNTY REMONUMENTATION PROGRAM

JUL 06 1998

CORNER APPROVED BY PEER GROUP ON DECEMBER 12, 1994

LAND CORNER RECORDATION CERTIFICATE

REGISTER'S OFFICE }
Mecosta County, } ss.

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in MECOSTA (County) Located In: _____ Corner Code # _____

1. Public Land Survey T 16N R 10 W E-04
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Received for Record, the 29
 day of June A.D., 1998
 at 3:15 o'clock P.M., and Recorded
 in Liber _____ of _____
 on Page _____

Joanne Brown
 Register of Deeds
 Register of Deeds
 Mecosta County
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JAMES G. KNAPP, in a field survey on SEPTEMBER 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: ONLY ONE CORNER MAY BE RECORDED ON THIS CERTIFICATE.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, JOHN HODGSON, SET POST IN APRIL, 1838, CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM CORNER COMMON TO SECTIONS 8, 9, 16 AND 17, AND WITNESSED: ELM 8" S58°W 14 LINKS (9.24 FEET)
 BEECH 9" N36°E 17 LINKS (11.22 FEET)

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, DATED JULY 21-22, 1921, BY D. L. FOSTER, SHOW A BEARING AND DISTANCE OF N1°-10'W, 2660.2' TO THE CORNER COMMON TO SECTIONS 4, 5, 8, AND 9, WITH CORNER WITNESSED:
 F. P. S58°-45'E 27.9'
 MAPLE 10" S86°-45'W 26.2'

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY PATRICK A. SALISBURY, P.S. 13594, ON SEPT. 25, 1972, AND RECORDED IN LIBER 10, PAGE 72, AND NOTES CORNER AS "FOUND IRON", AND WITNESSED: NAIL - 8" TRI. ELM DUE W. 27.42'
 NAIL - 12" MAPLE N28°E 84.15'
 NAIL - 22" MAPLE DUE E. 26.17'

CERTIFICATE OF SURVEYS AS PER P. A. 132 OF 1970, BY CLINTON E. COLE, P.S. 17615, ON DEC. 31, 1974, AND RECORDED IN LIBER 10, PAGES 282 AND 283, AND ON FEB. 20, 1975, AND RECORDED IN LIBER 10, PAGES 297 AND 298 AND NOTES CORNER AS "5/8 ROD", AND WITNESSED: 12" TRI. ELM S87°W . 27.42'
 12" W. OAK N26°E 84.18'
 14" MAPLE S88°E 26.20'

CORNER RECORDED AS PER P. A. 74 OF 1970, BY CLINTON E. COLE, P.S. 17615, ON SEPT. 30, 1975, AND RECORDED IN LIBER 1, PAGE 182, AND CORNER NOTED AS "FOUND 5/8" RE-BAR IN N. & S. GRAVEL ROAD", AND WITNESSED: TRIPLE 12" ELM S87°W 27.42'
 14" MAPLE S88°E 26.20'
 12" W. OAK N26°E 84.18'
 CONC. MONUMENT S88°E 33.00'

**APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 OF 1990**

James G. Knapp
 CHAIRMAN
 DATE DEC. 12, 1994

CONTINUED ON REVERSE SIDE


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" X 18" RE-BAR, IN SURFACE OF GRAVEL ROAD, AT 24" DEEP FOUND 1 1/2" X 18" FLAT IRON, 3' WEST OF CENTER OF 220TH. AVENUE (22' GRAVEL), AFTER BITUMINOUS PAVING ON JUNE 10, 1998, CORNER IS 3.6 FEET WEST OF CENTERLINE OF 20' BITUMINOUS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-04, 1/4 CORNER COMMON TO SECTIONS 8, AND 9, T16N-R10W.
 FOUND 5/8" X 18" RE-BAR, AND AT 24" DEEP FOUND 1 1/2" X 18" FLAT IRON, AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.
 REMOVED THE 5/8" X 18" RE-BAR AND SET IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, INSIDE OF A HIGHWAY MONUMENT BOX.
 SET 60d SPIKE W/REMONUMENTATION WITNESS TAG IN WEST SIDE 14" BUR OAK AZ. 22°, 103.96 FEET
 FOUND CONCRETE MONUMENT AZ. 84°, 33.00 FEET
 SET 60d SPIKE W/REMONUMENTATION WITNESS TAG IN NORTH SIDE 15" BUR OAK AZ. 118°, 38.52 FEET
 SET 60d SPIKE W/REMONUMENTATION WITNESS TAG IN S.W. SIDE 18" BUR OAK AZ. 160°, 92.70 FEET
 SET 60d SPIKE W/REMONUMENTATION WITNESS TAG IN N.E. SIDE TRIPLE 8" WILLOW AZ. 291°, 40.72 FEET

Signed by James G. Knapp Date JUNE 18, 1998
 Surveyor's Michigan License No. 25853



SURVEY &
REMONUMENTATION

JUL 06 1998

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

CONTINUED FROM REVERSE SIDE

CERTIFICATE OF SURVEYS AS PER P. A. 132 OF 1970, BY JOHN I. NELSON, P.S. 21273, ON MARCH 21, 1978, AND RECORDED IN LIBER 10, PAGES 511 - 515, AND NOTES CORNER AS, "FOUND 5/8" RE-BAR 3' WEST OF THE CENTER OF 220TH. AVENUE AND IN LINE WITH FENCE GOING WEST", AND WITNESSED:

TRIPLE 12" ELM STUMP	S87°W	27.42'
14" MAPLE	S88°E	26.20'
12" W. OAK	N26°E	84.18'
CONC. MONUMENT	S88°E	33.00'

CORNER RECORDED AS PER P. A. 74 OF 1970, BY DOUGLAS W. HOOTH, P.S. 7966, ON MAY 18, 1978, AND RECORDED IN LIBER 1, PAGE 435, AND CORNER NOTED AS "FOUND 5/8" RE-ROD FLUSH WITH GRAVEL SURFACE", AND WITNESSED:

N75°E	26.18 FT.	20" MAPLE
N25°E	84.14 FT.	12" OAK
S80°E	39.00 FT.	12" OAK