

**SURVEY & REMONUMENTATION MECOSTA COUNTY REMONUMENTATION PROGRAM**

MAR 03 1999

CORNER APPROVED BY PEER GROUP ON NOVEMBER 13, 1998

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

**SECTION**

For corners in

MECOSTA  
(County)

Located In:

Corner Code #

'98 DEC 28 A8:37

- |                                    |   |     |   |     |      |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey              | T | 16N | R | 10W | G-13 |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
| 2. Property Controlling in Section | S |     | T |     |      |
|                                    | S |     | T |     |      |
| 3. Miscellaneous Property in Sec.  | S |     | T |     |      |
|                                    | S |     | T |     |      |

*James Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on NOVEMBER 10, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990  
*James G. Knapp*  
CHAIRMAN  
DATE NOV. 13, 1998

NOTE: Only one corner may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, JOHN HODGSON, SET POST ON OCT. 14, 1837. POST PLACED 40.00 CHAINS (2640.00 FEET) FROM SOUTH 1/4 CORNER, SECTION 34, AND WITNESSED: SUGAR 12" N41°E 44 LINKS (29.04 FEET)  
SUGAR 8" N63°W 55 LINKS (36.30 FEET)

NOTES IN COUNTY SURVEYOR'S RECORD BOOK NO. 1, PAGE 127, DATED JUNE 28-29, 1903, BY DON B. ROBEN, NOTES CORNER AS, "STAKE", AND SHOWS A DISTANCE OF 2640' TO SOUTH 1/4 CORNER, SECTION 33.

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, DATED MAY 17, 1930, NOTE CORNER BEING AT STATION 28+35 WITH NORTH 1/4 CORNER, SECTION 4, T15N-R10W BEING AT STATION 0+00.

CORNER RECORDED ON LAND CORNER RECORDATION CERTIFICATE IN LIBER 1, PAGE 36, FROM MSHD FORM 280, BY HARLAN J. PTASZENSKI, SURVEY CHIEF, DATED JULY 9, 1964, AND NOTED AS, "FOUND 1/2" T IRON WITH BRASS CAP FLUSH WITH SURFACE OF BIT. NEAR CENTER OF E & W RD. & CENTER OF RD. TO NORTH", AND WITNESSED: TEL. POLE N24°W 64.56'  
32" W. CHERRY N45°E 63.10'  
TEL. POLE S69°E 64.84'

CORNER RECORDED AS PER P.A. 74 OF 1970, BY JACK E. PIERSON, P.S. 19305, IN LIBER 1, PAGES 186 - 187, ON SEP. 30 1975 AND NOTED AS, "FOUND "T" IRON - ACCEPTED AS CORNER", AND SHOWS A DISTANCE OF 174.42' TO N.W. CORNER, SECTION 3, T15N-R10W, AND WITNESSED: T.P. N24°W 64.56'  
32" W. CHERRY N45°E 63.10'  
T.P. S69°E 64.84'

CORNER RECORDED AS PER P.A. 74 OF 1970, BY DOUGLAS W. HOOTH, P.S. 7966, IN LIBER 1, PAGE 293, ON MAR. 24, 1977 AND NOTED AS, "FOUND "T" IRON IN BIT. RD. FLUSH, 1.0' SOUTH C/L E-W RD. & IN LINE WITH CTR. OF RD. NORTH", AND WITNESSED: S50°E 46.15' FE. POST  
S45°W 35.80' T. POLE  
N25°W 64.57' T. POLE  
S10°E 28.73' FE. POST

CORNER RECORDED AS PER P.A. 74 OF 1970, BY GERALD J. GRAY, P.S. 17741, IN LIBER 1, PAGE 500, ON AUG. 14 1979 AND NOTED AS, "FND. T IRON", AND WITNESSED: S35°W T. POLE 35.66'  
N40°W 8" TWIN MAPLE 96.20'  
N15°E 20" MAPLE 99.25'

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY ROBERT L. WETHERELL, P.S. 24624, ON APR. 2, 1996, AND RECORDED IN LIBER 12, PAGES 36 - 38, AND NOTES CORNER AS, "T" IRON ", AND SHOWS A DISTANCE OF 2642.73' TO THE SOUTH 1/4 CORNER, SECTION 33, T16N-R10W.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND "T" IRON, BURIED 3" BELOW BITUMINOUS ROAD SURFACE, AT 10" DEEP FOUND 1/2" X 30" IRON ROD, IN CENTERLINE OF 13 MILE ROAD (20' BITUMINOUS), AND 7' WEST OF CENTERLINE OF 210<sup>TH</sup>. AVENUE (20' BITUMINOUS - NORTH).


**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-13, CORNER COMMON TO SECTIONS 33 AND 34, T16N-R10W.  
FOUND "T" IRON AND 1/2" X 30" IRON ROD, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

REMOVED THE "T" IRON, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTMENT MONUMENT, AND WITNESSED:  
FOUND NAIL IN WEST SIDE 20" MAPLE AZ. 20°, 99.30 FEET  
FOUND NAIL IN N.W. SIDE UTILITY POLE AZ. 232°, 36.10 FEET  
SET 60d SPIKE W/REMONUMENT TAG IN NORTH SIDE UTILITY POLE AZ. 258°, 92.93 FEET  
N.E. CORNER, SECTION 4, T15N-R10W (COUNTY REMONUMENTMENT MONUMENT) AZ. 272°, 174.60 FEET

Signed by *James G. Knapp* Date DECEMBER 21, 1998

Surveyor's Michigan License No. 25853



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS JAN. 28, 1988  
REVISED MAY 1994  
REVISED JAN. 1998  
ADAPTED FOR WORD PROCESSING