

MECOSTA COUNTY REMONUMENTATION PROGRAM
CORNER APPROVED BY PEER GROUP ON 12 DECEMBER 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MECOSTA Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 16 N R 10 W _____ M-7 _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Joanne Brown
 Register of Deeds
 Mecosta County

'95 NOV -2 AM 12

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Matthew McClung, in a field survey on December 11 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: ONLY ONE CORNER MAY BE RECORDED ON THIS CERTIFICATE.

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by Deputy Surveyor John Hodgson on 13 October 1837. Volume 2 Field Notes Pages 138, set wood post.
 10" Beech N67W 53 lks.
 8" Beech S40W 13 lks.


Page 175 County survey Records. Date 4-28-15, by Willets, recorded as a 3" tile.
 Corner Fence Post NE 37.0'
 Elm Stump West 49.8'
 H. F. Anderson on 10-1932. Fence post West 26.5 feet.
 Road Plans April 30, 1919, 3" tile. Corner fence post NE 37.0' Elm Stump West 49.8' Fence West 26.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 20 penny spike at surface. Removed spike and dug to 24" below surface and found nothing. Hired backhoe and dug to 3' and found solid clay tile. Placed Mecosta County Monument over Tile 6" below surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M-7. Mecosta County Monument, which is a 3" brass cap mounted on a 2 1/2 pipe, 36" in length, and is accepted as a careful and faithful reestablishment of the position of the original corner.
 Power Pole N54E 99.14 feet
 Power Pole S62E 78.41 feet
 East most of 3 telephone pedestals S34E 51.87 feet.
 20" White Ash S12W 216.03 feet



**APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990**

James S. Knapp
 CHAIRMAN
 DATE DEC 12, 1994

Signed by Matthew McClung Date December 11, 1994

Surveyor's Michigan License No. 13037