

MECOSTA COUNTY REMONUMENTATION PROGRAM
CORNER APPROVED BY PEER GROUP ON 12 DECEMBER 1994

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Joanne Brown
 Register of Deeds
 Mecosta County

'95 NOV -2 A11:13

For corners in MECOSTA Located In: Corner Code #
 (County)

1. Public Land Survey T 16 N R 10 W M-8
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Matthew McClung, in a field survey on December 11 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: ONLY ONE CORNER MAY BE RECORDED ON THIS CERTIFICATE.

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by Deputy Surveyor John Hodgson on 13 October 1837. Volume 2 Field Notes Page 138, set post.
 Beech 8" S49W 37 lks.
 Beech 8" N49W 26 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set Mecosta County monument 9.0' East of straight line and equal distant between section corners. Corner is 6' North of in line corner post in East R/W fence, and does not fit any fences to West. Corner is 5' West of Road Center Line.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M-8. Mecosta County Monument, which is a 3" brass cap mounted on a 2 1/2 pipe, 36" in length, and is accepted as the best available evidence of the position of the original corner.
 3" W. Ash N86E 27.81 feet
 Power Pole N50W 23.48 feet
 Telephone Pedestal N56W 11.08 feet
 Iron and Cap #13037 East 33.00 feet

**APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 343 of 1990**
James H. Knapp
 CHAIRMAN
 DATE DEC 12, 1994

Signed by Matthew McClung Date December 11, 1994
 Surveyor's Michigan License No. 13037