

MECOSTA COUNTY REMONUMENTATION PROGRAM
CORNER APPROVED BY PEER GROUP ON 12 DECEMBER 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MECOSTA
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 16N R 10W _____ M-9 _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Joanne Brown
 Register of Deeds
 Mecosta County

'95 NOV -2 AM 1:13

Register of Deeds Stamp & File Number

I, Matthew McClung, in a field survey on December 11 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: ONLY ONE CORNER MAY BE RECORDED ON THIS CERTIFICATE.

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by Deputy Surveyor John Hodgson on 13 October 1837. Volume 2 Field Notes, set post.
 16" Hemlock S45W 18 lks.
 15" Hemlock N59W 171 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod and 3' tile filled with cinders at surface. Removed tile and bend rod north. Set Corner along south side of tile to a depth of 30" and placed Mecosta County Monument over tile.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M-9. Mecosta County Monument, which is a 3" brass cap mounted on a 2 1/2 pipe, 36" in length, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 24" Red Oak N15E 4 feet
- 10" Soft maple West 8.37 feet
- 4" White Pine S10W 10.90 feet.
- 24" White Pine S75E 9.25 feet
- Down Cedar fence post at corner.

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knepp
 CHAIRMAN
 DATE DEC 12, 1994

Signed by Matthew McClung Date December 11, 1994
 Surveyor's Michigan License No. 13037