

APPROVED LAND CORNER RECORDATION CERTIFICATE
 P.A. 345 OF 1990
 MIDLAND COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

445

For Corners in 11/13/99
Midland
 (County)

- | | | |
|--------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T. <u>13N</u> R. <u>1E</u> | <u>E-7</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat | | |
| 5. Private Claims | | |

STATE OF MICHIGAN
 MIDLAND COUNTY
 RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 26, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1832 Thomas
 77.60 Intersect Meridian 7.40 N of
 Corner 12 & 13 T13N, R1W
 Beech 12 N44E 37
 Pine 12 S67E 55
 1915 Gibbs, CSR
 Stone around old corner
 Pine Stp. N76W 53
 Meas. East 37.60 & North 40.44

1977 Lapham LCRC #432
 Fd 3/4" Iron in Mon. Box
 S45E 67.61 P.P.
 N45E 74.00 Fence Cor.
 S70W 57.68 4" Maple
 West 70.61 10" Maple

SURVEY &
 RECONSTRUCTION

FEB 25 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 3/4" Iron bar in Mon. Box. Excavated and found remains of old wood stake at 24" depth. Found all 1977 witnesses and measured East 2479.12 (Gibbs 2481.6) to F-7. Searched but could not find standard corner to South. E-7 is 4 feet West of C.L.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped Midland Co. Remon Corner P.S. #27458 in existing Mon. Box. Accepted as best available evidence of the original position of the corner.

Witnesses:
 N42°E, 106.82 N & T in 26" Oak
 S40°E, 67.50 N & T in P.P. (OBT)
 S70°W, 58.06 N & T in 10 x 14 x 4 Maple (OBT)
 S85°W, 69.99 N & T in 12 x 5 x 10 x 14 Maple (OBT)

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



Date 12-1-99

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971