

APPROVED LAND CORNER
 P.A. 345 OF 1990 **LAND CORNER RECORDATION CERTIFICATE**
 MIDLAND COUNTY **Filing Requirement of Act 74, Mich. P.A. 1970**

446

STATE OF MICHIGAN
 MIDLAND COUNTY
 RECORDED

11/12/1999 *JMA*

For Corners in
Midland

12/7/1999 2:59:31 PM

SCOTT I. HAINES
 REGISTER OF DEEDS

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>13N</u> R. <u>1E</u>	<u>F-7</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5		4			3		2			1
3													
4		7	8		9			10		11			12
5													
6		18	17		16			15		14			13
7													
8		19	20		21			22		23			24
9													
10		30	29		28			27		26			25
11													
12		31	32		33			34		35			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1832 Thomas 40.35 1/4 Sec Post W. Ash 20 S75E 58 Maple 24 N50W 42 41.50 stream 10 S.W.	1977 Lapham Set 1/2" rerod South 38.70 Fence Cor S80E 83.70 N.W. Cor Railing N80E 83.80 S.W. Cor Railing N40W 47.70 20" Maple
1915 Gibbs. CSR Old 1/4 Cor. stone deep in ground set large stone on top to bring Mon. to surface of road Meas. East 40.32, West 37.60	

1999 Corner was witnessed
 by MCRC prior to paving

**SURVEY &
 REMONUMENTATION**

FEB 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 12" rerod in Mon. Box 0.3 feet below surface of new asphalt pvm't. Found and checked M.C.R.C. witnesses to monument. Found four 1977 witnesses. Meas. West 2479.12 (Gibbs 2481.6) and measured East 2658.32 (Gibbs 2661.12). Raised Mon. Box with 3 inch monument ring. Corner fall at S.P.M.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped Midland Co. Remon Corner P.S. #27458 in raised Mon. Box. Accepted as best available evidence of the original position of the corner.
 Witnesses:
 N34°E, 46.88 N & T in 13" Ash
 South 38.52 N & T in Fence Post (OBT)
 S80°E, 83.88 Top Cen. I-beam Post Bridge Rail (OBT)
 N80°E, 84.12 Top Cen. I-beam Post Bridge Rail (OBT)
 N57°W, 63.45 N & T in 30" Oak

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



Date 12-1-99