

APPROVED LAND CORNER

P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE  
MIDLAND COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

449

12/12/1999

For Corners in  
Midland

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 13N R. 1E I-12  
T. \_\_\_\_\_ R. \_\_\_\_\_  
T. \_\_\_\_\_ R. \_\_\_\_\_
- 2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
MIDLAND COUNTY  
RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 29, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1832 Thomas  
40.00 1/4 Sec. Post  
Beech 12 S72W 20  
Ironwood 6 N77E 32

1909 Gibbs, CSR  
Anchor Post NE 30  
S.E. Corner of culvert 24  
Meas. 80.20 I-11 to I-13

SURVEY &  
REMONUMENTATION

FEB 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 12" pipe over old 1/2" x 36" rerod in Mon. Box on N. Bank of Drain Ditch E & W. Cor is 1.7 feet W of C.L. new asphalt pvm't. Meas North 2651.00 to I-11, turned 179° 56' 10" Left and meas South 2641.72 feet to I-13. I-11 to I-13 meas 5292.72 (Gibbs 5293.2).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped Midland Co. Remon Corner P.S. #27458 in existing Mon. Box. Accepted as best available evidence of original position of the corner.

Witnesses:  
N46°E, 86.50 N & T in P.P. (South Pole)  
S67°E, 24.12 Top. Cen E. End 48" Conc. Pipe  
S69°W, 55.70 N & T in P.P.  
N30°W, 46.24 Top. Cen North pipeline marker

Signed by Mark R. Robison

Surveyor's Michigan License No. 27458



Date 12-1-99

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1983