

SURVEY &  
REMONUMENTATION

NOV 07 1994

COMMISSION

REMON. COR. K-9, MT. HALEY TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

*Jeff 2/10/94*

56

For corners in  
Midland

(County)

Located in: Corner Code #

- |  |  |            |
|--|--|------------|
| 1. Public Land Survey                            | T <u>13N</u> R <u>1E</u>               | <u>K-9</u> |
|  | T <u>   </u> R <u>   </u>              | <u>   </u> |
|  | T <u>   </u> R <u>   </u>              | <u>   </u> |
|  | T <u>   </u> R <u>   </u>              | <u>   </u> |
| 2. Property Controlling<br>in Section            | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
| 3. Miscellaneous<br>Property in Sec.             | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
| 4. Lot No. <u>   </u> , Recorded Plat <u>   </u> |  |            |
| 5. Private Claims <u>   </u>                     |  |            |

STATE OF MICHIGAN  
MIDLAND COUNTY  
FILED

24 FEB 94 3:15 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A B C D E F G H I J K L M

2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RODNEY CLAYPOOL, in a field survey on NOVEMBER 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- |   |  |
|---|--|
| <p>K-9 Corner common Sec. 23, 24, 25, and 26<br/>Wood post Government survey 1832<br/>Beech 12", N 87 Deg W, 10 L (6.6')<br/>Beech 15", S 29 Deg E, 16 L (10.56')<br/>Survey by F.T. Gibbs 1905<br/>Old corner post found, set new oak post stones around<br/>Survey by D. Whittier L 1 P 265 (1972)<br/>found 3/4" iron in mon box<br/>N 45 Deg W, tag in 24" Oak, 51.10'<br/>N 30 Deg W, tag in telephone pole, 49.40'<br/>S 45 Deg E, tag in power pole, 65.15'<br/>(LCRC Dec, 26, 1972)<br/>Survey by D. Whittier 1977<br/>Found 3/4" pipe in mon box</p> | <p>LCRC #257 P. Lapham 1975<br/>found mon box<br/>S 50 Deg E, 65.22', power pole<br/>S 30 Deg W, 96.80', 30" Maple<br/>N 60 Deg W, 51.13', 30" Oak<br/>LCRC #410 H. Fluharty 1976, Found pipe in mon box<br/>power pole, S 62 Deg W, 66.56'<br/>power pole, S 57 Deg E, 65.18'<br/>36" Oak, N 58 Deg W, 51.05<br/>Survey by D. Ledy L 4 P 592 (1989)<br/>Found 3/4" pipe<br/>NW, 51.35', to spike in NE side 24" Oak<br/>WSW, 27.55', to top 1" iron pipe cemented in HDWL<br/>SE, 65.14', to old nail and tag in utility pole</p> |
|---|--|



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-9 Corner Common to Sec. 23, 24, 25, and 26  
Found 3/4" pipe in mon box per recorded survey L 1 P 265, and L 4 P 592; LCRC #257; LCRC 410

Corner K-9 was approved for remonumentation at a Peer Review Committee Meeting on FEB. 10, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-9 Corner common to Sec. 23, 24, 25 and 26  
3/4" pipe in mon box per rec. survey L 1 P 265; L 4 P 592 LCRC #257 LCRC #410 and is accepted as the best available evidence of the position of the original corner  
Replace 3/4" pipe with a 3/4" pipe and brass cap stamped Midland Co. Remon cor PS 29241  
S 30 Deg W, 96.80', nail and disc in 24" Maple N 60 Deg W, 51.32', nail and plastic disc in 28" Oak  
S 35 Deg W, 96.41', nail and plastic disc in 24" Maple S 45 Deg E, 65.19', nail and plastic disc in power pole  
S 55 Deg W, 66.61', nail and disc in power pole

Signed by Rodney D. Claypool Date 02-23-94

Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971

Revised May 14, 1971

Revised Jan., 1983