

SURVEY & REMONUMENTATION

APR 28 1995

**APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY**

COMMISSION

**REMON. COR. K-10, MT. HALEY TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

137

For corners in Midland
(County)

	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>1E</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

8 NOV 94 9:24 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on February 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-10 Corner common to Sections 25 and 26

- Government survey 1830's (wood post)
- Survey by F Gibbs, 1905, (post and stone)
- Survey by J. Schafer, 1979, (found pipe)

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 Corner common to Sections 25 and 26

Found 3/4" pipe (replaced with 5/8" rod and brass cap in mon box) per surveys by F. Gibbs and J. Schafer.

Corner K-10 was approved for remonumentation at a Peer Review Committee Meeting on Nov. 2, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 Corner common to Sections 25 and 26

Found 3/4" pipe (replaced with 5/8" rod and brass cap stamped Midland Co. Remon Cor. PS 29241 in mon box) per surveys by F. Gibbs and J. Schafer; and is accepted as the best available evidence of the accepted position of the corner.

N 85 Deg W, 43.23', nail and on N face power pole
S 60 Deg E, 29.02', notch in north end CMP

N 40 Deg W, 81.97', nail and plastic disc in 6" Elm clump
S 15 Deg W, 171.02', nail and plastic disc in power pole

Signed by Rodney O. Claypool

Date Nov 2 - 1994

Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983

