

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

SURVEY &  
REMONUMENTATION

FEB 24 1998

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

358

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T 14N R 1W	G-13
	T 13N R 1W	G-1
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
MIDLAND COUNTY  
FILED &  
REMONUMENTATION  
11 DEC 97 12:02 P.M.  
  
BEVERLY J THAYER  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1831 Clark  
Wit.-Hemlock 16 N27E 21  
Pine 31 N60W 14
  - 12-06-71 Whittier, L.C.R.C. 114  
Wit.-same as 11-10-71
  - 10-20-80 Lapham, L.C.R.C. 541  
1 x 3" bar  
Wit.-N45W 54.90 P.P.  
N45E 50.27 Brace P.P.  
S45W 49.57 Brace P.P.
  - 11-10-71 Whittier (132) 1-18  
Sleigh shoe  
Wit.-S35W 49.65 tag in Guy Pole  
N45W 54.85 tag in P. Pole  
N45E 50.27 tag in Guy Pole

2-22-84 MacDonald  
Wit.-NE 50.2 U. Pole  
NW 55.0 U. Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 3/8" x 18" iron, sleigh shoe, and crockery. Meas North 2650.92 to G-12.

Corners, G-13, T14N, R1W, & G-1, T13N, R1W, were approved for remonumentation at a Peer Review Committee Meeting on August 1, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:  
N48E 50.20', nail & tag, Guy pole  
N38W 54.90', nail & tag, P.P.  
S57W 49.66', nail & tag, Brace pole  
S60E 53.18', nail & tag, P.P.

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 10-31-97

