

SURVEY & REMONUMENTATION

FEB 24 1998

APPROVED P.A. 345 OF 1990 MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

SECTION 360

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

8/31/97 JRS

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T 14N R 1W T 13N R 1W	H-13 H-1 ✓
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

STATE OF MICHIGAN MIDLAND COUNTY FILED 2

REMONUMENTATION 11 DEC 97 12:03 P.M.

BEVERLY J THAYER REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, MARK R. ROBISON, in a field survey on July 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1831 Clark Post
- Wit.-Elm 13 N84 1/2E 46
- Pine 35 N08W 17
- 10-75 Schafer (132) 1-956
- Fd. 2" Pipe
- Wit.-North 12.56 tag in P.P. Stub
- North 50 degrees - 44.56 tag in P.P.
- N40W 75.59 tag in Oak Clump
- 10-20-80 Lapham, L.C.R.C. 527
- Fd 3/4" Pipe
- Wit.-South 32.85 Capped Iron
- North 12.75 Post
- N60E 44.65 P.P.
- N60W 52.30 6" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 18" pipe two feet deep in new constructed road. Found one 1975 witness. Meas. East 2635.08 (Schafer 2634.98) to I-13. Did not find 2" pipe. Major road re-construction has removed all other witnesses. Found old fence to South 32 ft. West.

Corners, H-13, T14N, R1W, & H-1, T13N, R1W, were approved for remonumentation at a Peer Review committee Meeting on 08/31/97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:

- N45W 75.59', nail & tag, in Oak Clump (OBT)
- N43E 40.08', nail & tag, P.P
- N61W 73.45', nail & tag, Twin 12" oak
- S45W 76.62', nail & tag, 14" W. Oak
- S29E 72.72', nail & tag, 13" W. Oak

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 10-31-97

