

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

221

6/6/95 *[Signature]*

For corners in

| | | |
|---------------------------------------|--------------------------|----------------|
| <u>MIDLAND</u> (County) | Located In: | Corner Code ## |
| 1. Public Land Survey | T <u>13N</u> R <u>1W</u> | <u>H-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
MIDLAND COUNTY
FILED

19 JUL 95 10:53 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, PAUL B. LAPHAM, in a field survey on MAY, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- H-9: 1/4 Corner common to Sections 22 & 27
 - 1852 AUSTIN BURT, POST, ELM 12" S44°W 36 LKS, BIRCH 14" N57°E 17 LKS.
 - 1901 GIBBS, POST OLD CORNER WELL PERSERVED
 - 11-09-72 HUNTER, REFERENCE N.-S. 1/4 LINE (132) 1-277
 - 10-28-76 JOHN MARTIN, SET 3/4" IRON PIPE ON C BIT RD. E&W

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in doossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- H-9: 1/4 Corner common to Sections 22 & 27
 - Set 5/8"x36" re-rod in gravel road on line with G-9 & found iron at 1/8 cor. between G-9 & H-9. Meas. G-9 to 1/8 corner, 1329.98' (Gibbs recorded 20.15') set H-9 1329.98' from 1/8 corner. Corner falls 8' South of C road with deep ditch on South side. Local resident says road has been rebuilt with under drain in location of corner. Corner does not fit centerline of road per Martin Survey, but the deep ditch on South side of road supports the location 8' south of centerline.

REMONUMENTATION
NOV 4 1995
COMMISSION

Corner, H-9 was approved for remonumentation at a Peer Review Committee Meeting on 6-6, 1995.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- H-9: 1/4 Corner common to Sections 22 & 27
 - Set 5/8" x 18" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Monument Box per survey by Gibbs. Accepted as best available evidence of the accepted position of the corner.
 - S78°E 274.03' - N&T IN POWER POLE
 - S01°E 51.13' - N&T IN POWER POLE
 - S82°W 322.51' - N&T IN POWER POLE
 - NORTH 28.58' - 2" DIA. GAS LINE VALVE



Signed by Paul B. Lapham Date 6-12-95
Surveyor's Michigan License No. 9433