

9/12/96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

276

For corners in

<u>MIDLAND</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>1W</u>	<u>1-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

27 NOV 96 2:52 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on NOVEMBER 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27	●	26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1852 BURT
SET 1/4 SEC. POST
WIT.-ELM 24" N46°E 55 LKS.
ELM. 40" S84°W 4 LKS.

9-24-01 GIBBS
STONE WITH DRAG TOOTH UNDER
40.12 TO I-9, 40.16 TO I-11

6-12-95 LAPHAM, L.C.R.C.
SET MIDLAND COUNTY REMON
CORNER AT I-9

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND I-9 BY LAPHAM FOUND 1/8 CORNER BETWEEN I-9 & I-10 BY GIBBS. FOUND I-11 IRON & TILE IN MON. BOX
SET I-10 1323.55 FEET SOUTH OF 1/8 CORNER ON LINE WITH AND 2647.10 FEET (GIBBS 2647.92') SOUTH OF I-9
AND 2649.75 FEET (GIBBS 2650.56') NORTH OF I-11 CORNER FALLS 6' WEST OF CENTERLINE GRAVEL ROAD.

Corner, I-10 was approved for remonumentation at a Peer Review Committee Meeting on SEP 12, 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. P.S. 9433".
ACCEPTED AS BEST AVAILABLE EVIDENCE OF PERPETUATION OF THE C.S.R. CORNER.

WITNESSES:
S84°E, 32.28' - NAIL & TAG IN 14" R. OAK
S38°W, 97.88' - NAIL & TAG IN POWER POLE (NORTH POLE)
S80°W, 34.75' - NAIL & TAG IN 5" TWIN ASH (NORTH TREE)
S15°W, 102.48' - PHONE RISER



Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 10-4-96