

**SURVEY &
REMONUMENTATION**

JAN 21 1999

APPROVED LAND COUNCIL
P.A. 845 OF 1998
MIDLAND COUNTY

MIDLAND County Remonumentation SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

382

For corners in 11/24/98 JBR

_____ MIDLAND _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T13N R01W	K-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K-3:** 1852 Burt
South 80.13 Cor of Sec 1-2-11-12
Wit-1)W. Pine 26" N68E 36
2)W. Pine 12" S73W 17
- 11-17-13 Gibbs
Piece of Buggy Axel set in Survey of 1&2
Meas West 40.12 & South 40.17
(Survey Sec 1.)
- 9-13 Gibbs CSR
Set 1/2 of Steel Buggy Axel at proportional measurement
Meas West 80.02 & North 39.80
(Survey Sec 2.)
- 9-29-13 Gibbs CSR (same as 9-13 above)
Measured East 39.60 & North 39.80
(Survey Sec 1.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-3:** Found 3/4" x 18" Pinch Pipe. Excavated to three feet and found no other evidence. Measured West 2644.70 (Gibbs 2647.92) feet to 1/4 corner. Measured North 2626 to Fence line (Gibbs 2626.80) but could not find corner. Measured East 2624.02 (Gibbs 2613.6) to 1/4 corner. Accepted pipe for corner.
- Corner, K-3, was approved for remonumentation at a Peer Review Committee Meeting on 11/24/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-3:** Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S.27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
N62W 89.72', nail & tag, P.P.
N51E 48.00', nail & tag, P.P.
S24E 72.26', nail & tag, P.P.
S42E 75.62', nail & tag, 14" Ash



Signed by Mark R. Robison

Date 12-09-98

Surveyor's Michigan License No. 27458