

SURVEY &
REMONUMENTATION

NOV 07 1994

COMMISSION

REMON. COR. A-9, INGERSOLL TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

APR 2/10/94

52

For corners in
Midland

(County)

Located in: Corner Code #

1. Public Land Survey

T 13N R 2E A-9

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
MIDLAND COUNTY
FILED

24 FEB 94 3:14 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on DECEMBER 6, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-9 Corner common to Section 19 and 30

Wood post Government survey 1832
Black Ash 8" N 31 1/2 Deg E, 17 L, (11.22')
Black Ash 6", S 55 1/2 Deg E, 25 L (16.5')

Survey by P. Ciosek 1984, found 3/4" pipe
NW 39.5' to N. end CMP
SW 32.0' to S. end CMP

Survey by D. Whittier 1970, found 3/4" pipe
5.43' South of NE cor Sec. 25 Mt. Haley Twp.,
T13N-R1E
Survey by J. Schafer 1974, found corner

Survey by D. Ledy 1990, found 3/4" pipe
South, 5.45' from 1/2" pipe SE cor Sec.
24, Mt. Haley Twp., T13N-R1E



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 Corner common to Sec. 19 and 30
Found 3/4" pipe per surveys by D. Whittier, J. Schafer, P. Ciosek and D. Ledy

Corner A-9 was approved for remonumentation at a Peer Review Committee Meeting on FEB 10, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 Corner common to Sec. 19 and 30

Found 3/4" pipe (removed and set 3/4" pipe with brass cap stamped Midland Co. Remon Cor. PS 29241 in monument box) per surveys by D. Whittier, J. Schafer, P. Ciosek and D. Ledy and is accepted as the best available evidence of the position of the original corner.
S 30 Deg W, 90.82', nail and plastic disc in power pole North, 5.46', 3/8" rod NE corner Section 25, Mt. Haley Township, T13N-R1E
S 60 Deg W, 32.15', S. end 48" CMP 0.17' East of controlling East Mt. Haley Township (T13N-R1E) line (M-9 to M-10)
S 45 Deg E, 39.62', E end 15" CMP
N 30 Deg W, 98.89', Nail and plastic disc in power pole 98.89'

Signed by Rodney D. Claypool

Date 02-23-94

Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971

Revised May 14, 1971

Revised Jan., 1983