

SURVEY &  
REMONUMENTATION

NOV 07 1994

COMMISSION

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

*JJG 2/10/94*

54

REMON. COR. A-10, INGERSOLL TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Midland \_\_\_\_\_  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 13N R 2E	A-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
MIDLAND COUNTY  
FILED

24 FEB 94 3:15 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													


I, RODNEY CLAYPOOL, in a field survey on DECEMBER 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-10 West 1/4 of Sec. 30

Survey by D. Whittier 1970, set 1" axle shaft at prorated off set distance at NW cor (A-9) and SW cor (A-11) of Sec. 30  
Due East, nail and disc in cor fence post, 14.94'  
N 80 Deg W, nail and disc in power pole, 53.75'  
Due North 10.30' 1/2" pipe E 1/4 cor Sec. 25, Mt. Haley Twp., T13N-R1E, on line with fence to East



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10 West 1/4 of Sec. 30  
Found nothing, set 5/8" rod and brass cap in monument box 10.30' south of E 1/4 cor Sec. 25 Mt. Haley Twp., T13N-R1E, and 53.75' from nail in disc in power pole N 80 Deg W, per survey by D. Whittier according to remaining witness.

Corner A-10 was approved for remonumentation at a Peer Review Committee Meeting on FEB 10, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10 West 1/4 of Sec. 30

5/8" rod and brass cap stamped Midland Co. Remon Cor. PS 29241 in monument box per D. Whittier survey 1970 and is accepted as the best available evidence of the position of the original corner.  
N 80 Deg W, 53.75', nail and disc in power pole  
N 30 Deg E, 118.69', nail and plastic disc in telephone pole  
N 35 Deg W, 128.69', SE cor HSE foundation  
S 45 Deg E, 41.44', Nail and plastic disc in 12" Pine North, 10.30', 1/2" pipe W 1/4 cor Sec. 25, Mt. Haley Twp., T13N-R1E  
0.10' East of controlling East Mt. Haley Township (T13N-R1E) line

Signed by Rodney D. Claypool Date 02-23-94