

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

27 NOV 96 2:54 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

For corners in

MIDLAND (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>2E</u>	G-5
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on OCTOBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1831 PARKE
SET POST
WIT.-SUGAR S88°E 19 LKS.
ELM 10" S55°W 12 LKS.
 - 7-30-79 SCHAFFER, L.C.R.C.
FOUND 1/2" ROD IN MON. BOX
WIT.-S45°W, 42.18' - TAG IN TELE. POLE
N45°W, 80' - TAG IN TELE. POLE
N30°E, 62.17' - TAG IN TELE. POLE
 - 4-30-79 SCHAFFER, (132) 2-812
FOUND BOLT SPIKE IN MON. BOX
WIT.-N45°W, 59.05' - NAIL & TAG IN TELE. POLE
N45°E, 68.70' - CENTER 8" ASH
S45°E, 44.5' - NAIL & TAG IN POWER POLE
 - 5-16-81 JONES, (132) 3-219
SAME AS 7-30-79
 - 1-27-84 MACDONALD, (132) 3-540
FOUND MON. BOX

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 1/2"x1/2"x12" SPIKE IN CONCRETE IN MONUMENT BOX 3 FEET SOUTH OF INTERSECTION OF CENTER-LINES.
FOUND 4-30-79 WITNESSES. MEAS. NORTH 2653.38' (SCHAFFER 2653.08') TO G-4
IT APPEARS THAT THE 7-30-79 WITNESSES ARE IN ERROR.

Corner, G-5 was approved for remonumentation at a Peer Review Committee Meeting on SEP 12, 1996.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. P.S. 9433" IN MON. BOX.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:
N45°W, 59.05' - NAIL & TAG IN TELE. POLE (OBT)
N45°E, 68.70' - NAIL & TAG IN 10" ASH (OBT)
S45°E, 44.50' - NAIL & TAG IN POWER POLE (OBT)
N65°E, 70.55' - NAIL & TAG IN 6" ASH CLUSTER (NORTH TREE)



Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 10-4-96