

SECURITY &
REMC RECONSTITUTION

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

APR 23 1995

REMON. CORNER G-7 INGERSOLL TOWNSHIP
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

163

For corners in
Midland
(County)

1. Public Land Survey

Located in: Corner Code #
T 13N R 2E G-7

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

STATE OF MICHIGAN
MIDLAND COUNTY
Remonumentation & File

12 DEC 94 9:47 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on March 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-7 Corner common to Sections 15, 16, 21 and 22

- Government survey 1830, set wood post
- Survey by F. Gibbs, 1902, (found post with iron at side)
- Survey by Dow, 1954, (3/4" pipe)
- Survey by J. Schafer, 1971, 1974, 1977, 1979, (3/4" pipe in mon box)
- Survey by M. MacDonald, 1983, (found 3/4" pipe)
- LCRC D. Whittier, 1972, (3/4" pipe)

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 Corner common to Sections 15, 16, 21 and 22

Found 3/4" pipe (replaced pipe with 3/4" pipe and brass cap in mon box) per surveys by F. Gibbs, Dow, J. Schafer, M. MacDonald, and LCRC by Whittier.

Corner G-7 was approved for remonumentation at a Peer Review Committee Meeting on DEC 5, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 Corner common to Sections 15, 16, 21 and 22

Found 3/4" pipe (replaced pipe with 3/4" pipe and brass cap stamped Midland Co. Remon Cor. PS 29241 in mon box) per surveys by F. Gibbs, J. Schafer, M. MacDonald, and LCRC by D. Whittier; and is accepted as the best available evidence of the accepted position of the corner.

- S 45 Deg E, 44.51', SW corner of SW'LY guard post on bridge
- N 45 Deg E, 73.55', nail and plastic disc in power pole
- S 45 Deg E, 51.28', nail and plastic disc in power pole
- N 75 Deg W, 165.44', centerline brine line valve (screw)
- East 4', centerline N and S road
- North 11', centerline E and W road

Signed by Rodney D. Claypool Date 12-09-94

Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971

Revised May 14, 1971

Revised Jan. 1992

