

SURVEY &
REMONUMENTATION

NOV 07 1994

COMMISSION

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

949 1/13/94

44

REMON. COR. I-9, INGERSOLL TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Midland

(County)	Located in:	Corner Code #
1. Public Land Survey	T 13N R 2E	I-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

24 JAN 94 2:53 P.M.

Register of Deeds Stamp & File Number
BEVERLY J. THAYER
REGISTER OF DEEDS

I, RODNEY CLAYPOOL, in a field survey on DECEMBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-9 Corner common to Section 22, 23, 26, 27

Wood stake Government survey 1830's
Sycamore 11", N 48 Deg E, 8 L. (5.28')
Sycamore 7", S 81 1/2 Deg W, 20 L (13.20')

Survey by L. McGinnis 1975, Found "T" Iron
SE 36.2' to stop sign
NE 44.0' to telephone pole.
SW 72.4' to power pole

Surveys by F. Gibbs 1915 set iron rod, 3' long stones around
Survey by D. Whittier 1972, found T-bar with punch mark
N 40 Deg E, tag in telephone. 44.13'
S 55 Deg E, 50.81', end rivet S end 18" CMP
S 45 Deg W, tag in power pole
soil conservation service bench mark 72.20'

Survey by J. Schafer 1979, found corner
LCRC by J. Martin 1976, found T-bar
SW 72.18' to BM in face power and telephone pole
NE 44.12' to nail and cap in W face telephone pole



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 Corner common to Sec. 22, 23, 26, 27

Found 60 penny spike in mon box per surveys by F. Gibbs, D. Whittier, L. McGinnis and J. Schafer and LCRC by J. Martin
Apparently 60 penny spike set by Road Commission

Corner I-9 was approved for remonumentation at a Peer Review Committee Meeting on JAN. 13, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Corner common to Sec. 22, 23, 26, 27

Found 60 penny spike in mon box (set 5/8" rod with brass cap stamped Midland Co. Remon Cor. PS 29241) and is accepted as the best available evidence of the position of the original corner.
S 35 Deg E, 54.46', nail and plastic disc in power pole
N 40 Deg E, 44.21', nail and plastic disc in telephone pole
S 60 Deg E, 50.85', S rivet on S. end 18" CMP
S 40 Deg W, 37.71', centerline S. end 24" CMP

Signed by Rodney D. Claypool Date 01-20-94

Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971

Revised May 14, 1971

Revised Jan., 1983