

NOV 07 1994

*JG 1/13/94*

COMMISSION

41

REMON. COR. J-5, INGERSOLL TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Midland

(County)

Located in: Corner Code #

1. Public Land Survey

T 13N R 2E J-5

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

24 JAN 94 2:53 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on DECEMBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

A B C D E F G H I J K L M

2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-5 Corner common to Section 11 and 14

Wood stake Government survey 1830's

Survey by M. Hunter 1968, set 3/4" pipe and mon box

Sycamore 16", N 81 Deg E, 12', (7.92')  
Sycamore 9", N 88 Deg W, 15' (9.90')


Survey by J. Schafer 1973, 1977, found 3/4" pipe in mon box

Survey by M. Hunter 1953, set 3/4" pipe  
stone around

Survey by J. Jones 1984, found 3/4" pipe in mon box

Survey by D. Whittier 1964, 1968, found corner

Survey by D. Ledy 1988, found 3/4" pipe



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5 Corner common to Section 11 and 14

Found 3/4" pipe in mon box per surveys by M. Hunter, D. Whittier, J. Schafer, J. Jones and D. Ledy

Corner J-5 was approved for remonumentation at a Peer Review Committee Meeting on JAN 13, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 Corner common to Section 11 and 14

Found 3/4" pipe in mon box (set 5/8" rod and rod and brass cap stamped Midland Co. Remon Cor. PS 29241) per surveys by M. Hunter, D. Whittier, J. Schafer, J. Jones and D. Ledy and is accepted as the best available evidence of the position of the original corner.

N 40 Deg W, 61.17', nail and plastic disc in power pole

N 70 Deg W, 108.57', nail and plastic disc in 30" Elm

S 75 Deg W, 63.25', nail and plastic disc in mail box post

S 45 Deg W, 37.72', centerline S. end 24" CMP

Signed by Rodney D. Claypool

Date 01-20-94

Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971

Revised May 14, 1971

Revised Jan., 1983