

L. C 4 P. 310

12/11/18

Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Craig W. McVean

Field Survey Date: Oct. 29, 2018

For corner(s) in: Midland

County

Original Public Land Survey Corner

Corner Code

S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____

Property Controlling Corner

Corner Code

S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____

Property Corner

Corner Code

S	<u>4</u>	T	<u>13N</u>	R	<u>2W</u>	<u>11</u>
S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____

Protracted Public Land Survey Corner

Corner Code

S	<u>4</u>	T	<u>13N</u>	R	<u>2W</u>	<u>F2</u>
S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														1
2		6		5		④		3		2		1		2
3														3
4		7		8		9		10		11		12		4
5														5
6		18		17		16		15		14		13		6
7														7
8		19		20		21		22		23		24		8
9														9
10		30		29		28		27		26		25		10
11														11
12		31		32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

F2 - C 1/4 - Cor. Sec. 4, T13N, R2W
- None

11 - SW 1/16 Cor. Sec. 4, T13N, R2W
- None

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

F2 – C ¼ Cor. Sec. 4, T13N, R2W –
Set 2" Alum. Cap on 5/8" x 34" iron rebar
at intersection of ¼ lines per standard BLM
procedure. Centerline of Old 2-track WSW-ENE
is 4.5'± South.

11 – SW 1/16 Cor. Sec. 4, T13N, R2W
Set 2" Alum. Cap on 5/8" x 34" long iron rebar per
standard BLM procedure. Centerline of N-S Hevel
Drain Branch One is 46' East.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

F2 – C ¼ Cor. Sec. 4, T13N, R2W
Stamped 2" Aluminum Cap on 5/8" x 34" long
iron rebar.
Set Blue Composite Post w/ Loc. Tag 1' SW
N32°E 26.96' to set N & T in SE side 8" Red Maple
S43°E 32.60' to set N & T in NE side 6" Red Maple
S45°W 30.46' to set N & T in NW side 5" R. Maple
N42°W 19.55' to set N & T in NE side Triple 7" R.
Maple

11 – SW 1/16 Corner Sec. 4, T13N, R2W
Stamped 2" Aluminum Cap on 5/8" x 34" long iron
rebar
Set Blue Composite Post with Loc. tag 1' SE
N48°W 9.04' to set N & T in SW side 8" Cherry
N29°E 26.10' to set N & T in W. side 16" R. Maple
S58°E 43.54' to set N & T in S. side 12" R. Maple
S3°W 31.61' to set N & T in E. side 14" W. Oak



Craig W. McVean

Craig W. McVean

12/11/2018

Date

Professional Surveyor's License No.: 39088

Prepared By:
Craig W. McVean
Michigan Dept. of Natural Resources
8015 Mackinaw Trail
Cadillac, Michigan 49601