

L, C 4, P. 314

12/11/18

Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Craig W. McVean

Field Survey Date: Oct. 30, 2017

For corner(s) in: Midland County

Original Public Land Survey Corner **Corner Code**

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

Property Controlling Corner **Corner Code**

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

Property Corner **Corner Code**

S 10 T 13N R 2W 1

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

Protracted Public Land Survey Corner **Corner Code**

S 10 T 13N R 2W H4

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														1
2	6		5		4		3		2		1		2	
3								●					3	
4	7		8		9		10		11		12		4	
5													5	
6	18		17		16		15		14		13		6	
7													7	
8	19		20		21		22		23		24		8	
9													9	
10	30		29		28		27		26		25		10	
11													11	
12	31		32		33		34		35		36		12	
13													13	
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

H4 - C 1/4 corner Sec. 10, T13N, R2W - None

1 - W 1/16 corner common to Section 3 & 10, T13N, R2W - None

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

H4 – C ¼ corner Sec. 10, T13N, R2W –
Set stamped 2" Aluminum Cap on 5/8" x 34" long iron rebar at intersection of ¼ lines per Standard BLM procedure. RR tie post with wolver wire fence remains to the west is N08°35'W 121'.

1 – W 1/16 corner common to Sec. 3 & 10, T13N, R2W.
Set stamped 2" Aluminum Cap on 5/8" x 34" long rebar per standard BLM procedure.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

H4 – C ¼ corner Sec. 10, T13N, R2W –
Stamped 2" Aluminum Cap on 5/8" x 34" long iron rebar.
Set Blue Composite Post with Loc. Tag 1' North N64°E 4.53' to set N & T in NW side 8" R. Maple N17°W 11.38' to set N & T in E. side 11" R. Maple N59°W 11.17' to set N & T in N. side 5" Oak S03°W 31.75' to set N & T in W. side 6" W. Oak

1 – W 1/16 corner common to Sec. 3 & 10, T13N, R2w.
Set Blue Composite Post with Loc. Tag 1' SE S67°E 31.77' to set N & T in N. side 27" Oak S25°E 75.99' to set N & T in W. side 9" R. Maple S25°W 18.45' to set N & T in W. side 6" R. Maple N39°W 45.19' to set N & T in NE side 5" R. Maple



Craig W. McVean
Craig W. McVean

12/11/2018
Date

Professional Surveyor's License No.: 39088

Prepared By:
Craig W. McVean
Michigan Dept. of Natural Resources
8015 Mackinaw Trail
Cadillac, Michigan 49601