

11/12/96 JRG

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

20 DEC 96 2:06 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

For corners in

<u>MIDLAND</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>2W</u>	<u>F-7</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on AUGUST, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1852 BURT, G.L.O.  
WIT.-OLD COR. SET POST  
ELM 7" S55 1/2°W 26 LKS.  
B. ASH 14", N28°E 55 LKS.

3-29-71 WHITTIER, UNRECORDED SURVEY  
WIT.-FOUND S 1/4 CORNER.

NO DATE GIBBS  
WIT.-EST. 1/4 SEC. COR. AT AVG. DIST.  
40.23' TO E-7, 40.23' TO G-7.

9-22-69 WHITTIER, UNRECORDED SURVEY  
WIT.-REFERENCES S 1/4 CORNER.  
NOTES STATE CORNER SET BY DOUBLING  
OVER DISTANCE BETWEEN S.W. CORNER &  
1/8 COR. S.W. TO S 1/4 IS 2649.4.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4"x18" PIPE IN ASPHALT PAVEMENT, MEAS. EAST 2659.14' TO G-7 (GIBBS 2655.18') MEAS. WEST 2649.64' TO E-7 (GIBBS 2655.18') (WHITTIER 2649.4) FOUND NO OTHER EVIDENCE OF CORNER OR OCCUPATION. ACCEPTED PIPE AS CORNER.

Corner, F-7 was approved for remonumentation at a Peet Review Committee Meeting on 11-12 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. P.S. 9433".  
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:  
N70°W, 157.84' - NAIL & TAG IN POWER POLE.  
S06°W, 80.45' - NAIL & TAG IN POWER POLE.  
S66°E, 53.36' - SOUTH END 36" C.M.P.  
N75°E, 56.90' - NORTH END 36" C.M.P.



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 12-19-96