

**SURVEY &  
REMONUMENTATION**

**APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY**

APR 28 1995

126

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

11/03/94 *[Signature]*

For corners in

MIDLAND (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>2W</u>	<u>1-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

B NOV 94 9:22 A.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

I, PAUL B. LAPHAM, in a field survey on JULY, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1-7: Section Corner common to Sections 14, 15, 22 & 23
- 1852 - Austin Burt, No Witnesses Given
- 02/28/02 - Gibbs, Set W. Oak Post, Pine Stump N 65°E 32 lks, Pine Stump N 84°W 58 lks, C.S.R. 1-48
- 04/05/02 - Gibbs, Same as above, C.S.R. pp. 116-117, 142-145
- 03/06/03 - Gibbs, Post Old Corner, C.S.R. 1-36
- 09/27/74 - David Whittier, 3/4" Pipe, (1) NW to Nail & Flag, NE side, Power Pole, 56.65' L.C.R.C. 371
- (2) NW to Petroleum Line Marker, 33.25' (3) SW to Petroleum Line Marker, 32.6'
- 08/ /83 - Thomas Mueller, Set PK Nail from Previous Accessories, Witnessed as above, L.C.R.C. 593
- 11/04/92 - Gerald Gray, 1/2" Rod in Mon. Box (132) 4-929
- (4) 55° AZ. 81.61' - 4" White Birch
- (1) 322° AZ. 56.64' - Service Pole
- (5) 149° AZ. 52.63' - Top Apex, Phone Box
- (6) 213° AZ. 32.67' - Top @ C.M.P.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1-7: Section Corner common to Sections 14, 15, 22 & 23
- Found 1/2" X 7" Threaded Rod; 3/4" x 12" pipe in Monument Box. Excavated to 2-1/2 feet and found no further evidence.
- Found Recorded Witnesses 1, 4, 5 & 6.

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, 1-7 was approved for remonumentation at a Peer Review Committee Meeting on 11-02, 1994.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1-7: Section Corner common to Sections 14, 15, 22 & 23
- Set 5/8" x 18" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Monument Box.
- 55° AZ. 81.61' - 4" White Birch (4)
- 322° AZ. 56.64' - Service Pole (1)
- 149° AZ. 52.63' - Top Apex, Phone Box (5)
- 213° AZ. 32.67' - Top @ C.M.P. (6)



Signed by Paul B. Lapham  
Surveyor's Michigan License No. 9433

Date 11-03-94