

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

357

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T 13N R 2W	K-11
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
MIDLAND COUNTY  
FILED &  
REMONUMENTATION  
11 DEC 97 12:02 P.M.  
  
BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, **MARK R. ROBISON**, in a field survey on **July 1**, 19 **97** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1852 Burt Old Cor. 9-10-75 Whittier (132) 1-471  
 Wit. B. Ash 12 S37W 36 Elm 14 N25E 50 3/4" Pipe  
 10-24-02 Gibbs, C.S.R. S45E 70.0 N&D in P.P.  
 Post Old Cor. SE 23.2 Top rivet in 48" CMP  
 4-23-03 Gibbs, C.S.R. SW 31.7 Top rivet in 48" CMP  
 Old Post NW 103.87 SE Cor Brick School  
 11-04-75 Whittier, L.C.R.C. 375  
 3/4" Pipe Lined and Meas. off recovered points  
 Wit. same as 9-10-75

8-25-87 Jones (132) 4-62  
 Mon box (no witnesses)  
 8-16-93 Jones (132) 5-29  
 No witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd 3/4" pipe in Mon box. Found all 1975 witnesses. 1975 survey indicates 2638.66 feet West to J-11 (C.S.R. 2636.04). 1987 survey measured South 2656.28 to K-12 (C.S.R. 2663.1) (Meas. 2656.64).

Corner, K-11 was approved for remonumentation at a Peer Review Committee Meeting on August 1, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
 N45W 103.72' SE Cor Brick School (OBT)  
 N40E 63.86', nail & tag, 6" Pine  
 S16E 70.00', nail & tag, P.P. (OBT)  
 S44E 104.58', nail & tag, 18" Elm

Signed by Mark Robison  
 Surveyor's Michigan License No. 27458

Date 10-31-97

