

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MIDLAND

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------|
| 1. Public Land Survey | T <u>13N</u> R <u>2W</u> | K-12 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

356

STATE OF MICHIGAN
MIDLAND COUNTY
FILED &
REMONUMENTATION
11 DEC 97 12:02 P.M.

BEVERLY J. THAYER
Register of Deeds Stamp & File Number
REGISTER OF DEEDS

I, **MARK R. ROBISON**, in a field survey on **July 1**, 19 **97** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1852 Burt Post
- Wit.-B. Ash 10 S43W 25
- Y. Birch 8 N30E 20

10-24-02 Gibbs, C.S.R.
Stone deep in ground set in old culvert then filled

8-25-87 Jones (132) 4-62
Fd. 3/4" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe. Excavated to 3 feet; found no further evidence. Meas. South 2665.44 to K-13 (C.S.R. 2666.4) (1987 survey 2665.09). Meas. North 2656.64 to K-11 (C.S.R. 2663.1) (1987 Survey 2656.28). Observed fence line of occupation to East.

Corner, K-12 was approved for remonumentation at a Peer Review Committee Meeting on August 1, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of accepted position of the corner.

- Witnesses:
- N88E 58.40', nail & tag, P.P.
 - S04E 338.48', nail & tag, P.P.
 - N10E 333.86', nail & tag, P.P.
 - N76E 37.94', nail & tag, R.R. Tie Fence Post

SURVEY &
REMONUMENTATION

FEB 24 1998

SECTION

Date 10-31-97



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458