

APPROVED LAND CONVERSION  
P.A. 345 OF 1990  
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

353

For corners in

|                                       |                          |               |
|---------------------------------------|--------------------------|---------------|
| <u>MIDLAND</u><br>(County)            | Located In:              | Corner Code # |
| 1. Public Land Survey                 | T <u>13N</u> R <u>2W</u> | <u>K-13</u>   |
|                                       | T ___ R ___              | _____         |
|                                       | T ___ R ___              | _____         |
|                                       | T ___ R ___              | _____         |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___        | _____         |
|                                       | S ___ T ___ R ___        | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___        | _____         |
|                                       | S ___ T ___ R ___        | _____         |

STATE OF MICHIGAN  
MIDLAND COUNTY  
FILED  
REMONUMENTATION  
11 DEC 97 12:01 P.M.  
BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on July 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |   |    |   |    |   |    |   |    |   |    |   |    |   |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

- 1831 Clark  
Wit.-Beech 8 N63E 8  
Lynn 30 N29W 38
- 10-24-02 Gibbs, C.S.R.  
Gas Pipe
- 8-25-87 Jones (132) 4-62  
Shows K-13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" square iron at Closing Corner inside 1 1/4" x 13" pipe. Meas. 2631.30 (Jones 2630.68) to 3/4" pipe at L-13. Set K-13 at 22.44' West of Closing Corner (K-1) on line with K-1 and L-13 per Jones survey. Meas. North 2665.44 (Jones 2665.09) (C.S.R. 2666.4) to K-12. Meas. West 2630.24 to J-13 (C.S.R. 2650.66). Meas. East 2653.74 to L-13.

Corner, K-13 was approved for remonumentation at a Peer Review Committee Meeting on August 1, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:
- N34W 128.96' NE Cor Hse
  - N75E 191.04', nail & tag, P.P.
  - S13E 234.58', nail & tag, Oak
  - S67W 168.96' NW Cor Pole Barn

SURVEY &  
REMONUMENTATION

FEB 24 1998

SECTION

Date 10-31-97



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458