

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

297

REMON. COR. B-1, MIDLAND TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

11/12/96

For corners in  
Midland  
(County)

	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>2E</u>	<u>B-1</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
4. Lot No. <u>   </u> , Recorded Plat <u>   </u>		
5. Private Claims <u>   </u>		

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

13 DEC 96 2:05 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on JUNE 21, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-1 North 1/4 corner for Section 6 on north townline

Not set by Government survey

Survey by M. Hunter, 1967  
Survey by J. Schafer, 1974  
Survey by J. Schafer, 1974

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 North 1/4 corner for Section 6 on north townline

Corner in manhole top. (chiseled mark on rim, North, South, East, and West to make "+" at corner) per surveys by M. Hunter, J. Schafer, and LCRC by J. Schafer

Corner B-1 was approved for remonumentation at a Peer Review Committee Meeting on 11/12/96.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 North 1/4 corner for Section 6 on north townline

Corner in manhole top. (chiseled mark on rim, North, South, East, and West to make "+" at corner) per surveys by M. Hunter, J. Schafer, and LCRC by J. Schafer; and is accepted as the best available evidence of the position of the accepted corner.

S 50 Deg E, 55.54', nail and plastic disc in light pole  
N 60 Deg E, 35.95', pk nail in 4" x 4" mail box post  
N 10 Deg W, 50.33', nail and disc in power pole  
S 60 Deg W, 85.13', nail and disc telephone pole

Signed by Rodney D. Claypool

Date 12-11-96

Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971.

Revised May 14, 1971

Revised Jan., 1983

