

NOV 07 1994

COMMISSION

J.D. 2/24/94

REMON. COR. E-4, CITY OF MIDLAND LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

68

For corners in Midland

(County)

Located in: Corner Code #

- 1. Public Land Survey T 14N R 2E E-4
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN MIDLAND COUNTY REMONUMENTATION & FILED

15 MAR 94 9:02 A.M.

BEVERLY J THAYER REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on DECEMBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A B C D E F G H I J K L M

2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

A. Description of original monument and accessories and/or subsequent restoration:

E-4 Corner common to Sections 8 and 9

- Wood post Government survey 1830's Survey by M. Hunter 1963, The Gardens Subd.
- Hemlock 9", N 72 Deg W, 8 1/2 L (5.61') Survey by D. Ledy 1984
- Ironwood 6", N 73 Deg E, 24 L (15.84') Survey by M. MacDonald 1984, 1985 found mon box
- Survey by F. Gibbs 1932, iron top mon box centerline pavement of M-10 LCRC by A. Leach 1977, found mon box N 45 Deg E, 53.20', nail and tag in SW face of power pole
- Survey by M. Hunter 1946, Northpark Acres Subd. S 45 Deg E, 50.30' to NW face of power pole
- Survey by M. Hunter 1951, Northpark Acres No. 2 S 45 Deg W, 50.70' to top center of fire hydrant



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 Corner common to Sections 8 and 9

Found 1/2" rod in mon box (replaced rod with 3/4" pipe and brass cap) per surveys by M. Hunter, D. Ledy, M. MacDonald and LCRC by A. Leach

Corner E-4 was approved for remonumentation at a Peer Review Committee Meeting on FEB 24, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 Corner common to Sections 8 and 9

Found 1/2" rod in mon box (replaced rod with 3/4" pipe and brass cap stamped Midland Co. Remon Cor. PS 29241) per surveys by M. Hunter, D. Ledy, M. MacDonald and LCRC by A. Leach and is accepted as the best available evidence of the perpetuation of the accepted corner. N 45 Deg E, 64.42', nail and plastic disc in guy pole S 40 Deg E, 69.48', nail and plastic disc in power pole S 45 Deg W, 57.90', nail and plastic disc in light pole N 45 Deg W, 78.55', Southwesterly corner brick sign

Signed by Rodney D. Claypool Date 03-14-94

Surveyor's Michigan License No. 29241