

**REMON. COR. F-3, CITY OF MIDLAND
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

470

For corners in
Midland

(County)

Located in: Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>14N</u> R <u>2E</u> | <u>F-3</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

12/15/1999 8:26:43 AM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on July 23, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-3 1/4 Corner common to Sections 4 and 9

- Survey by Glo, 1830, set post
- Survey by F. Gibbs, 1897, found
- Survey by Spicer Engineering, 1954, set monument (Meadowbrook Woods No. 3)
- Survey by Hunter-Whittier, 1976, found monument
- LCRC by J. Jones, 1986, found concrete monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3 1/4 Corner common to Sections 4 and 9

Found concrete monument per surveys by F. Gibbs, Spicer Engineering, Hunter-Whittier and LCRC by J. Jones.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3 1/4 Corner common to Sections 4 and 9

Set brass cap stamped Midland Co. Remon Cor PS 29241 on concrete monument, and is accepted as the best available evidence of the position of the accepted corner.

- S 10 Deg W, 35.15', nail and plastic disc in power pole (Rec.)
- S 80 Deg E, 10.57', nail and plastic disc in 6" Maple
- N 80 Deg E, 7.26', nail and plastic disc in 10" Maple (Rec.)
- N 5 Deg E, 45.44', nail and plastic disc in 24" Ash
- South, 81', centerline Wheeler Road

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													



Signed by Rodney D. Claypool
Surveyor's Michigan License No. 29241

Date 12-11-99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983

REMONUMENTATION
P.A. 74 OF 1970
MIDLAND COUNTY

4/23/99

SURVEY &
REMONUMENTATION

FEB 09 2000

SECTION