

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

JAN 21 1999

REMON. COR. 1-6, MIDLAND TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION 399

For corners in
Midland
(County)

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER
REGISTER OF DEEDS

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>14</u> N R <u>2E</u> | <u>1-6</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RODNEY CLAYPOOL, in a field survey on JULY 21, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-6 Corner common to Sections 14 and 15
- Survey by Glo, 1830's, set post
Survey by A. Courtright, 1949
Survey by M. Hunter, no date
Survey by J. Schafer, 1979
Survey by J. Jones, 1990, 1996



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-6 Corner common to Sections 14 and 15
- Found 3/4" pipe per surveys by A. Courtright, M. Hunter, J. Schafer, and J. Jones

Corner I-6 was approved for remonumentation at a Peer Review Committee Meeting on August 17, 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-6 Corner common to Sections 14 and 15
- Found 3/4" pipe per surveys by A. Courtright, M. Hunter, J. Schafer, and J. Jones, replaced pipe with 5/8" rod and brass cap stamped Midland Co. Remon Cor. PS 29241, and is accepted as the best available evidence of the position of the accepted corner.
- N 32 Deg E, 47.67', SW bolt on signal light pole base
N 62 Deg W, 53.91', SW bolt on signal light pole base
S 32 Deg W, 48.06', NE bolt on signal light pole base
S 60 Deg E, 48.83', NE bolt on signal light pole base

Signed by Rodney D. Claypool Date 09-11-98

Surveyor's Michigan License No. 29241