

NOV 07 1994

2/24/94

COMMISSION

REMON. COR. I-9, CITY OF MIDLAND
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

72

For corners in
Midland

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

15 MAR 94 9:02 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

(County)	Located in:	Corner Code #
1. Public Land Survey	T 14N R 2E	I-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RODNEY CLAYPOOL, in a field survey on DECEMBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-9 Corner common to Section 22, 23, 26 and 27

Wood post Government survey 1830's
Fine 24 L (16.06')

Survey by M. MacDonald 1987, 1989,
found mon box in centerline road
N 36.34' to centerline track
NE 40.95' to SW bolt of railroad signal
NW 58.92' to SE bolt of rialroad signal

Survey by F. Gibbs 1902, 1906, set cedar post at side
of fence post said to be corner of section 22, 23, 26 and 27

Survey by Edmands Engineering 1977
found mon box in centerline road
N 36.34' to centerline track
NE 40.95' to SW bolt of railroad signal
NW 58.92' to SE bolt of railroad signal

Survey by J. Jones 1992
found 1/2" rod in mon box
North, N edge of S railroad track 34.00'
N 60 Deg E, SW bolt on railroad signal 40.89'
N 45 Deg W, SE bolt on railroad signal 58.83'
N 70 Deg E, nail in power pole 72.47'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 Corner Common to Sec. 22, 23, 26 and 27

Found 3/8" rod in mon box per surveys by F. Gibbs, Edmands Engineering, M. MacDonald and J. Jones

Corner I-9 was approved for remonumentation at a Peer Review Committee Meeting on FEB 24, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Corner common to Sec. 22, 23, 26 and 27

Found 3/8" rod in mon box (mon box and rod in concrete, could not remove; rod to close to side of box to set brass cap; left as found) per surveys by F. Gibbs, Edmands Engineering, M. MacDonald, and J. Jones and is accepted as the best available evidence of the perpetuation of the accepted corner

N 60 Deg E, 40.90', SW bolt on railroad signal base
N 70 Deg E, 72.78', nail and disc in power pole

N 45 Deg W, 58.85', SE bolt on railroad signal base
S 40 Deg W, centerline fire hydrant, 85.00'

Signed by Rodney D. Claypool Date 03-14-94

Surveyor's Michigan License No. 29241