

**REMON. COR. K-6, CITY OF MIDLAND
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

473

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

12/15/1999 8:26:43 AM

SCOTT I. HAINES
REGISTER OF DEEDS

For corners in
Midland
(County)

	Located in:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>2E</u>	<u>K-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on August 13, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-6 ¼ Corner common to Sections 13 and 14

Survey by Gio, 1830's, set post
Survey by M. Hunter, 1952, 1953, found ¾" pipe
Survey by J. Jones, 1989, found, Eagle Ridge Research Park No. 1 & Survey L 4 Pg 369
LCRC by J. Jones, 1997, found pk nail

SURVEY &
REMONUMENTATION

FEB 09 2000

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SECTION

K-6 ¼ Corner common to Sections 13 and 14

Found pk nail per surveys by M. Hunter, J. Jones and LCRC by J. Jones

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 ¼ Corner common to Sections 13 and 14

Replaced pk nail with 5/8" rod and brass cap stamped Midland Co. Remon Cor PS 29241 in monument box, and is accepted as the best available evidence of the position of the accepted corner.


S 88 Deg E, 65.19', nail in 12" Maple
S 11 Deg W, 129.78', pk nail in power pole (Rec.)
N 8 Deg W, 190.91', railroad spike in power pole
N 10 Deg W, 143.86', centerline top fire hydrant (Rec.)

Signed by Rodney D. Claypool
Surveyor's Michigan License No. 29241

Date 12-11-99

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1971
Revised Jan., 1983

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY



11/23/99 JSG